

**CNG Producing
Company**

May 5, 1992

RECEIVED

MAY 07 1992

**DIVISION OF
OIL GAS & MINING**

Mr. Ed Forsman
Dept. of the Interior
Bureau of Land Management
Vernal District Office
170 South 500 East
Vernal, UT 84078

RE: River Bend Unit
RBU 9-14F NE/4 of SE/4 of Sec. 14-T10S-R20E
RBU 13-17F SW/4 of SW/4 of Sec. 17-T10S-R20E
RBU 15-17E SW/4 of SE/4 of Sec. 17-T10S-R19E
RBU 5-22E SW/4 of SE/4 of Sec. 22-T10S-R19E

Dear Ed:

Enclosed please find Original and two copies of the subject applications.
Attachment to this application includes the following:

Attachment No. 1	Location
Attachment No. 2	Certification Statement
Attachment No. 3	BOP Stack Schematic
Attachment No. 4	Drilling Plan
Attachment No. 5	13 Point Surface Use Plan
Attachment No. 6	Water Source and Access Route
Attachment No. 7	Water Permit

CNG Producing Company is requesting all information be held confidential.

It would be appreciated if this permit could be expedited since drilling is planned to begin in June, 1992.

If you have any questions or need any further information, please feel free to contact me at (504) 593-7260 or our project engineer, David Linger, at (504) 593-7779. Thank you for your continued cooperation.

Sincerely,

Susan M. Hebert

Susan M. Hebert
Regulatory Reports Asst. II

cc: ~~Tony Seering - Utah Board of Oil, Gas & Mining~~

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
BUDGET BUREAU NO. 1004-0135
EXPIRES: MARCH 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir. Use "APPLICATION FOR PERMIT - " for such proposals

SUBMIT IN TRIPLICATE

RECEIVED

MAY 07 1992

1. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other	7. If Unit or CA, Agreement Designation River Bend Unit
2. Name of Operator CNG PRODUCING COMPANY	8. Well Name and No. 13-17F
3. Address and Telephone No. CNG Tower - 1450 Poydras Street, New Orleans, LA 70112-6000	9. API Well No.
4. Location of Well (Footage, Sec., T., R., M., or Survey Description) Surface - 646' FWL & 690' FSL of Sec. 17-T10S-R20E	10. Field and Pool, or Exploratory Area Island
	11. County or Parish, State Uintah, Utah

CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

TYPE OF ACTION

<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Abandonment	<input type="checkbox"/> Change of Plans
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Recompletion	<input type="checkbox"/> New Construction
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Plugging Back	<input type="checkbox"/> Non-Routine Fracturing
	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> Water Shut-Off
	<input type="checkbox"/> Altering Casing	<input type="checkbox"/> Conversion to Injection
	<input checked="" type="checkbox"/> Other - Variance in casing	<input type="checkbox"/> Dispose Water

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to the work.)*

Under Onshore Order #2, casing and cementing requirements, it states "All casing, except the conductor casing, shall be new or reconditioned and tested used casing that meets or exceeds API standards for new casing" the 8 5/8" 24# H-40 surface casing designed for this well and other wells in the River Bend Unit meets all of the above criteria for the order. The 8 5/8" casing is a limited service pipe which means it does not meet API standards. However, the pipe is new and was Hydro statically tested to 2,700 PSI which equals API standards for 9 5/8" 24# K-55 casing.

We respectfully submit this sundry and attached letter from the company the pipe was purchased from.

if any additional information is needed, please advise.

CONFIDENTIAL

14. I hereby certify that the forgoing is true and correct

Signed David L. Linger Title Senior Drilling Engineer Date May 5, 1992
David L. Linger #912

(This space for Federal or State office use)


Approved by _____ Title _____ Date _____
Conditions of approval, if any:

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*See Instructions on Reverse Side

**CNG PRODUCING CO.
WELL LOCATION PLAT
RBU 13-17F**

LOCATED IN THE SW $\frac{1}{4}$ OF THE SW $\frac{1}{4}$ OF
SECTION 17, T10S, R20E, S.L.B.&M.



SCALE: 1"=1000'

LEGEND & NOTES


- ◆ Original corner monuments found and used by this survey.

The General Land Office (G.L.O.) plat was used for reference and calculations, as was the U.S.G.S. quadrangle map.

SURVEYOR'S CERTIFICATE

I hereby certify that this plat was prepared from field notes of an actual survey performed by me, during which the shown monuments were found or established.

Jerry D. Allred
Jerry D. Allred, Registered Land
Surveyor, Cert. No. 3817 (Utah)



JERRY D. ALLRED & ASSOCIATES
Surveying & Engineering Consultants

121 North Center Street
P.O. Drawer C
DUCHESSNE, UTAH 84021
(801) 738-6382

1 May '92

79-128-242

DRILLING PLAN
APPROVAL OF OPERATIONS

May 5, 1992

Attachment for Permit to Drill

Name of Operator: CNG PRODUCING COMPANY
Address: CNG TOWER - 1450 POYDRAS STREET
NEW ORLEANS, LA 70112-6000

WELL LOCATION: Well No. 13-17F

Uintah, Utah

1. **GEOLOGIC SURFACE FORMATION**

Uintah

2. **ESTIMATE IMPORTANT GEOLOGIC MARKERS**

<u>Formation</u>	<u>Depth</u>
Wasatch Tongue	4150'
Green River Tongue	4500'
Wasatch	4650'
Chapita Wells	5390'
Uteland Buttes	6400'

3. **ESTIMATED DEPTHS OF ANTICIPATED WATER, OIL, GAS OR MINERALS**

<u>Formation</u>	<u>Depth</u>	<u>Remarks</u>
Wasatch Tongue	4150'	Oil Zone
Chapita Wells	5390'	Gas Zone
Uteland Buttes	6400'	Gas Zone

4. **PROPOSED CASING PROGRAM**

8-5/8", 24#/ft, H-40, 0'-350' - Cemented to Surface
5", 17#/ft, N-80 & K-55, 0'- 7600' - Cemented to Surface

5. **OPERATOR'S MINIMUM SPECIFICATIONS FOR PRESSURE CONTROL**

BOP stack has a 3000 psi working pressure. BOP will be pressure tested to 2,700 psi before drilling casing cement plug. Pipe rams will be operated daily and blind rams as possible.

6. The well is to be drilled with a DAP (Diamonium Phosphate)/KCL mud system maintaining a weight of approximately 9#/gal.

CONFIDENTIAL

7. AUXILIARY EQUIPMENT TO BE USED

1. Kelly Cock.
2. Full opening valve on floor with DP connection for use when Kelly is not in string.

8. TESTING, LOGGING, AND CORING PROGRAMS TO BE FOLLOWED

A mud logger will be used from 3,500' to TD. Possible DST in Wasatch Tongue. The logging program will include Dual Lateral/GR log TD to Surface, Density/Neutron - TD - 3,500' possible dipmeter and rotary cores over selected intervals.

9. ANTICIPATED ABNORMAL PRESSURES OR TEMPERATURES EXPECTED

No normal pressures are anticipated nor is the area known for abnormal temperatures. The formations to be penetrated do not contain H₂S gas. The anticipated bottom hole pressure is 2,610 PSI.

10. WATER SUPPLY

- A. Water to be used for drilling will be hauled from CNG's OSC #1 well located in Section 17-T10S-R20E. Application #54801 User's Claim - Code #49, Serial #801.
- B. No pipelines are anticipated. Hauling will be on the road(s) shown in Attachment No. 3.
- C. No water well is anticipated to be drilled at this time.

11. CEMENT SYSTEMS

SURFACE

+/-224 sks 25:75 Poz G cement, 2% S-I CaCl₂, .25#/sk D-29 Flake

PRODUCTION

Lead Slurry - 195 sk DS Hi-Lift, 3% D-44 Salt, 10#/sk D-42 Kolite, .25#/sk D-29 Celloflake.

Tail Slurry - 335 sk RFC 10-0 (thixotropic).

12. ANTICIPATED STARTING DATE AND DURATION OF THE OPERATIONS

Starting Date: June, 1992

Duration: 20 Days

CONFIDENTIAL

SURFACE CASING CEMENT PROGRAM

Set 8 5/8" casing in 12 1/4" open hole cement to surface. Volume calculated using 75% excess.

SPACER:

Pump 20 BBLS lightly gelled water followed by 5 BBLS fresh H₂O ahead of cement to water wet the well bore after air drilling. Displace with fresh water.

CEMENT SYSTEM

± - 224 SK 25:75 Poz G "Tail-In" Cement, 2% S-1 CaCl₂, .25#/sk D-29 Celloflake.

Weight	15.40 lb/gal
Yield	1.11 ft ³ /sk
Water	4.71 gal/sk

Thickening Time at 118° 1:42min.

Compressive Strength at 80°	8 hrs. 750 psi
	16 hrs. 1800 psi
	24 hrs. 2400 psi

CASING HARDWARE:

- 1 Cement Guide Shoe
- 1 Insert Float
- 3 Centralizers
- 1 Stop Ring
- 1 Thread Lock
- 1 Top Wood Plug

NOTE - DS will at no charge (unless used), in addition to the casing cement, have 100 sk of cement, CaCl₂ for 2% by volume, and 80' to 100' of 1" tubing on location for top out job should cement not be returned to surface.

CONFIDENTIAL

LONGSTRING CEMENT

Set 5 1/2" casing in a 7 7/8" open hole.

Lead cement slurry to fill from 750' above top pay zone to surface.

Tail cement slurry to fill from TD to 750' above the pay zone.

Both volumes are calculated using 15% excess.

SPACER:

(DAP Mud System) 20 BBL CW-100 (Sodium Silicate); 20 BBL Water

(KCL Mud System) 10 BBL water

Displace with 3% KCL water using .2% L-55 Clay Stabilizer in the first 50 bbl of displacement.

CEMENT SYSTEMS

Lead Slurry

± - 195 sk DS Hi-Lift, 3% D-44 Salt, 10#/sk D-42 Kolite, .25#/sk D-29 Celloflake.

Weight	10.80 lb/gal
Yield	3.91 ft ³ /sk
Water	24.40 gal/sk

Thickening Time at 180°	4hrs +
Compressive Strengths in 24 hrs.	375 psi
Fluid Loss	240 cc/30 min.

Tail Slurry

± - 335 sk RFC 10-0 (thixotropic).

Weight	14.20 lb/gal
Yield	1.61 ft ³ /sk
Water	7.91 gal/sk

Thickening Time at 165 deg. BHCT	min.
Compressive Strength in 12 hrs.	845 psi
24 hrs.	1470 psi

CONFIDENTIAL

Date NOS Received: _____

CONDITIONS OF APPROVAL
FOR THE SURFACE USE PROGRAM OF THE
APPLICATION FOR PERMIT TO DRILL

Company/Operator: CNG PRODUCING COMPANY

Well Name & Number: RBU 13-17F

Lease Number: U-013769-C

Location: SW/4 of SW/4 Sec. 17 T. 10S R. 20E

Surface Ownership: Bureau of Land Management

NOTIFICATION REQUIREMENTS

Location Construction - forty-eight (48) hours prior to construction of location and access roads.

Location Completion - prior to moving on the drilling rig.

Spud Notice - at least twenty-four (24) hours prior to spudding the well.

Casing String and Cementing - twenty-four (24) hours prior to running casing and cementing all casing strings.

BOP and Related Equipment Tests - twenty-four (24) hours prior to initiating pressure tests.

First Production Notice - within five (5) business days after new well begins or production resumes after well has been off production for more than ninety (90) days.

For more specific details on notification requirements, please check the Conditions of Approval for Notice to Drill and Surface Use Program.

CONFIDENTIAL

B. THIRTEEN POINT SURFACE USE PROGRAM:

Multipoint Requirement to Accompany APD

1. Existing Roads - describe the following and provide a legible map, labeled and showing:
 - a. Proposed wellsite as staked and access route to location, including distances from point where access route exists establish roads. (Actual staking should include tow directional reference stakes.)
 - b. Route and distance from nearest town or locatable reference point, such as a highway or county road, to where well access route leaves main road.
 - c. Access road(s) to location color-coded or labeled.
 - d. Plans for improvement and/or maintenance of existing roads. (Appropriate rights-of-way for off lease roads should be attached.)
2. Planned Access Roads--describe the following and provide a map of suitable scale indicating all necessary access roads (permanent and temporary) to be constructed or reconstructed, showing:
 - a. Length - 1,000' starting at access road to Mt Truel bridge
 - b. Width - 30 foot right-of-way with 18 foot running surface maximum.
 - c. Maximum grades - 8%
 - d. Turnouts - None
 - e. Drainage design - Route drainage around south sides of location
 - f. Location and size of culverts and/or bridges, and brief description of any major cuts and fills - None
 - g. Surfacing material (source) - Native
 - h. Necessary gates, cattleguards, or fence cuts and/or modification to existing facilities - None

(New or reconstructed roads are to be centerline-flagged at time of location staking.)

All travel will be confined to existing access road rights-of-way.

Access roads and surface disturbing activities will conform to standards outlined in the Bureau of Land Management and Forest Service publication: Surface Operating Standards for Oil and Gas Exploration and Development, (1989).

CONFIDENTIAL

The road shall be constructed/upgraded to meet the standards of the anticipated traffic flow and all-weather road requirements. Construction/upgrading shall include ditching, draining, graveling, crowning, and capping the roadbed as necessary to provide a well constructed safe road. Prior to upgrading, the road shall be cleared of any snow cover and allowed to dry completely. Traveling off the 30 foot right-of-way will not be allowed. Road drainage crossings shall be of the typical dry creek drainage crossing type. Crossings shall be designed so they will not cause siltation or accumulation of debris in the drainage crossing nor shall the drainages be blocked by the roadbed. Erosion of drainage ditches by runoff water shall be prevented by diverting water off at frequent intervals by means of cutouts. Upgrading shall not be allowed during muddy conditions. Should mud holes develop, they shall be filled in and detours around them avoided.

____ Right-of-Way Application needed.

____ The operator/lessee or his/her successor shall be responsible for all maintenance on cattleguards or gates associated with this oil and/or gas operation.

3. Location of Existing Wells - describe the following and provide a map or plat of all wells within a 1 mile radius of the proposed well location showing and identifying existing: (See attached map)

- a. Water wells - OSC #1
- b. Abandoned wells - None
- c. Temporarily abandoned wells - RBU 3-17F, RBU 16-19F
- d. Disposal wells - None
- e. Drilling wells - None
- f. Producing wells - RBU 8-18F, RBU 15-18F, 8510, RBU 12-18F, RBU 13-18F, RBU 1-19F, RBU 11-19F, RBU 6-20F, RBU 1-20F, RBU 9-20F, RBU 12-20F, RBU 11-16F, RBU 1-17F, RBU 3-17FX, RBU 11-17F, RBU 15-17F, 3-11500, 15-6661
- g. Shut-in wells - None
- h. Injection wells - None

4. Location of Existing and/or Proposed Facilities

- a. On well pad: Show the following existing area facilities and dimensions to be utilized if the well is successfully completed for production (detail painting plans and color if applicable):
 - (1) Tank batteries
 - (2) Production facilities
 - (3) Oil gathering lines
 - (4) Gas gathering lines - Map with pipeline route attached to production facility
 - (5) Injection lines
 - (6) Disposal lines
 - (7) Surface pits (separate application per NTL-2B requirements)

(Indicate if any of the above lines are buried.)

- b. Off well pad: Same as above. Off lease flowlines may require rights-of-way or special use permits, check with the District Office Realty Specialist. (Include a diagram of the proposed attendant lines, i.e., flowlines, powerlines, etc., if off well pad location.)

- (1) Proposed location and attendant lines shall be flagged off of well pad prior to archaeological clearance.
- (2) Dimensions of facilities
- (3) Construction methods and materials
- (4) Protective measures and devices to protect livestock and wildlife

Note: Operator has option of submitting information under 4A and B, after well is completed for production, by applying for approval of subsequent operations.

If storage facilities/tank batteries are constructed on this lease, the facility/battery or the well pad shall be surrounded by a containment dike of sufficient capacity to contain, at a minimum, the entire content of the largest tank within the facility/battery, unless more stringent protective requirements are deemed necessary by the authorized officer.

Tank batteries will be placed on the North

All permanent (on site for six months or longer) structures constructed or installed (including pumping units) will be painted a flat, non-reflective, earthtone color to match on of the standard environmental colors, as determined by the Rocky Mountain Five State Interagency Committee. All facilities will be painted within 6 months of installation. Facilities required to comply with O.S.H.A. (Occupational Safety and Health Act) will be excluded.

The required paint color is Desert Tan.

If at any time the facilities located on public land and authorized by the terms of the lease are no longer included in the lease (due to a contraction in the unit or other lease or unit boundary change), BLM will process a change in authorization to the appropriate statute. The authorization will be subject to appropriate rental or other financial obligation as determined by the authorized officer.

CONFIDENTIAL

5. Location and Type of Water Supply

- a. Show location and type of water supply, either by 1/4, 1/4 section on a map or by written description OSC #1 located in section 17-T10S-R20E
- b. State method of transporting water, and show any roads or pipelines needed.
- c. If water well is to be drilled on lease, so state. _____

*The operator will be responsible for acquiring the necessary permit to obtain water to be used for drilling activities.

6. Source of Construction Materials

- a. Show information either on map or by written description - _____.
- b. Identify if from Federal or Indian (tribal or allotted) land.
- c. Describe where materials such as sand, gravel, stone, and soil material are to be obtained and used.

*If fill materials are needed to construct roads or well sites, proper permits must be obtained from the Surface Management Agency, unless materials are obtained from a private source.

*A mineral materials application (is/is not) required.

7. Methods of Handling Waste Disposal

- a. Describe methods and location of proposed safe containment and disposal of each type of waste material, including:
 - (1) Cuttings - bury in pit
 - (2) Sewage - haul to sewer lagoon
 - (3) Garbage (trash) and other waste material - haul to disposal
 - (4) Salts - not used
 - (5) Chemicals - non-toxic only; evaporate in pits
- b. Provide a plan for eventual disposal of drilling fluids and any produced oil or water recovered during testing operations. _____

*Burning will not be allowed. All trash must be contained in a trash cage and hauled away to an approved disposal site at the completion of the drilling activities.

On BLM administered lands:

The reserve pit shall be constructed so as not to leak, break, or allow discharge.

The reserve pit (shall/shall not) be lined if necessary to conserve water.

"If a plastic nylon reinforced liner is used, it will be a minimum of 10 mil thickness with sufficient bedding (either straw or dirt) to cover any rocks. The liner will overlap the pit walls and be covered with dirt and/or rocks to hold it in place. No trash, scrap pipe, etc., that could puncture the liner will be disposed of in the pit. More stringent protective requirements may be deemed necessary by the A.O."

After first production, produced waste water will be confined to a lined pit or storage tank for a period not to exceed ninety (90) days. During the 90 day period, in accordance with NTL-2B, an application for approval of a permanent disposal method and location, along with required water analysis, shall be submitted for the AO's approval. Failure to file an application within the time allowed will be considered an incident of noncompliance.

On BIA administered lands:

All reserve pits will be lined with either native clay, commercial bentonite or plastic sufficient to prevent seepage. (If a plastic nylon reinforced liner is used, it shall be torn and perforated after the pit dries and before backfilling of the reserve pit.)

___ To protect the environment.
If the reserve pit is lined the operator will provide the BLM a chemical analysis of the fluids in that pit no later than 90 days after the well completion to determine the method for final reclamation of the reserve pit. If the elemental concentrations shown by the chemical analysis exceeds the requirements described by Part II, Standards of Quality for Waters of the State, Wastewater Disposal Regulations, State of Utah Division of Health, the contents and liner will be removed and disposed of at an authorized disposal site.

X To protect the environment (without a chemical analysis).

Reserve pits will be constructed so as not to leak, break, or allow discharge of liquids.

___ Storage tanks will be used if drill sites are located on tribal irrigable land, flood plains, or on lands under crop production.

After first production, produced waste water will be confined to a lined pit or storage tank for a period not to exceed ninety (90) days. During the 90 day period, in accordance with NTL-2B, an application for approval of a permanent disposal method and location, along with required water analysis, shall be submitted for the AO's approval. Failure to file an application within the time allowed will be considered an incident of noncompliance.

CONFIDENTIAL

8. Ancillary Facilities

Camp facilities or airstrips will not be allowed unless otherwise approved.

9. Well Site Layout--provide a plat (not less than 1" = 50') showing:

- a. Cross-sections of proposed drill pad with approximate cuts and fills and the relation to topography.
- b. Location of mud tanks, reserve, and flare pits, pipe racks, living facilities, and soil material stockpiles, etc. (Approval as used in this section means field approval of location.)
- c. Rig orientation, parking area, and access roads, etc.

The reserve pit will be located on the : Southeast corner

The flare pit will be located downwind of the prevailing wind direction on the South side
a minimum of 100 feet from the well head and 30 feet from the reserve pit fence.

The stockpiled topsoil (first four inches) will be stored on the: East end of location

Access to the well pad will be from the: West end

___ Diversion ditch(es) shall be constructed on the _____ side of the location (above / below) the cut slope, draining to the _____.

___ Soil compacted earthen berm(s) shall be placed on the _____ side(s) of the location between the _____.

___ The drainage(s) shall be diverted around the _____ side(s) of the well pad location.

___ The reserve pit and/or pad location shall be constructed long and narrow for topographic reasons _____.

___ The _____ corner of the well pad will be rounded off to avoid the _____.

Fencing Requirements

All pits will be fenced according to the following minimum standards:

- a. 39-inch net wire shall be used with at least one strand of barbed wire on top of the net wire (barbed wire is not necessary if pipe or some type of reinforcement rod is attached to the top of the entire fence).

CONFIDENTIAL

- b. The net wire shall be no more than 2-inches above the ground. The barbed wire shall be 3-inches above the net wire. Total height of the fence shall be at least 42-inches.
- c. Corner posts shall be cemented and/or braced in such a manner to keep the fence tight at all times when pit is shrunk for production pit.
- d. Standard steel, wood, or pipe posts shall be used between the corner braces. Maximum distance between any two posts shall be no greater than 16 feet.
- e. All wire shall be stretched, by using a stretching device, before it is attached to the corner posts.

The reserve pit fencing will be on three sides during drilling operations and on the fourth side when the rig moves off the location. Pits will be fenced and maintained until clean-up.

Each existing fence to be crossed by the access road shall be braced and tied off before cutting so as to prevent slacking of the wire. The opening shall be closed temporarily as necessary during construction to prevent the escape of livestock, and upon completion of construction the fence shall be repaired to BLM or SMA specifications. A cattleguard with an adjacent 16 foot gate shall be installed in any fence where a road is to be regularly travelled. If the well is a producer, the cattleguard (shall/shall not) be permanently mounted on concrete bases. Prior to a new road, crossing any fence located on federal land, or any fence between federal land and private land, the operator will contact the BLM, who will in turn contact the grazing permittee or owner of said fence and offer him/her the opportunity to be present when the fence is cut in order to satisfy himself/herself that the fence is adequately braced and tied off.

10. Plans for Restoration of Surface

a. Producing Location

Immediately upon well completion, the location and surrounding area will be cleared of all unused tubing, equipment, debris, materials, trash, and junk not required for production.

Immediately upon well completion, any hydrocarbons on the pit shall be removed in accordance with 43 CFR 3162.7-1.

If a plastic nylon reinforced liner is used, it shall be torn and perforated before backfilling of the reserve pit.

The reserve pit and that portion of the location not needed for production facilities/operations will be recontoured to the approximate natural contours. The reserve pit will be reclaimed within 6 months from the date of well completion. Before any dirt work takes place, the reserve pit must be completely dry and all cans, barrels, pipe, etc., will be removed.

Contact appropriate surface management agency for required seed mixture.

b. Dry Hole/Abandoned Location

At such time as the well is plugged and abandoned, the operator shall submit a subsequent report of abandonment and BLM will attach the appropriate surface rehabilitation conditions of approval.

On BIA administered lands:

Abandoned well sites, roads, or other disturbed areas will be restored to near their original condition. This procedure will include: (a) re-establishing irrigation systems where applicable, (b) re-establishing soil conditions in irrigated fields in such a way as to ensure cultivation and harvesting of crops and, (c) ensuring revegetation of the disturbed areas to the specifications of the Ute Indian Tribe or the BIA at the time of abandonment.

11. Surface Ownership:

Access Road: Bureau of Land Management
Location: Bureau of Land Management

"If the access road and/or location involves private or state agency owned surface, a copy of the surface owners agreement is required prior to approval of the APD. "

12. Other Additional Information

- a. The Operator is responsible for informing all persons in the area who are associated with this project that they will be subject to prosecution for knowingly disturbing historic or archaeological sites, or for collecting artifacts. If historic or archaeological materials are uncovered during construction, the operator is to immediately stop work that might further disturb such materials, and contact the authorized officer (AO). Within five working days the AO will inform the operator as to :

-whether the materials appear eligible for the National Register of Historic Places;

-the mitigation measures the operator will likely have to undertake before the site can be used (assuming in situ preservation is not necessary); and

-a time frame for the AO to complete an expedited review under 36 CFR 800.11 to confirm, through the State Historic Preservation Officer, that the findings of the AO are correct and that mitigation is appropriate.

If the operator wishes, at any time, to relocate activities to avoid the expense of mitigation and/or the delays associated with this process, the AO will assume responsibility for whatever recordation and stabilization of the exposed materials may be required. Otherwise, the operator will be responsible to mitigation costs. The AO will provide technical and procedural guidelines for the conduct of mitigation. Upon verification from the AO that required mitigation has been completed, the operator will then be allowed to resume construction.

- b. The operator will control noxious weeds along right-of-way for roads, pipelines, well sites, or other applicable facilities. A list of noxious weeds may be obtained from the BLM, or the appropriate County Extension Office. On BLM administered land it is required that a Pesticide Use Proposal shall be submitted, and given approval, prior to the application of herbicides or other pesticides or possible hazardous chemicals.
- c. Drilling rigs and/or equipment used during drilling operations on this well site will not be stacked or stored on Federal Lands after the conclusion of drilling operations or at any other time without BLM authorization. However, if BLM authorization is obtained, it is only a temporary measure to allow time to make arrangements for permanent storage on commercial facilities. (The BLM does not seek to compete with private industry. There are commercial facilities available for stacking and storing drilling rigs.)

On BIA administered land:

Operator's employees, including subcontractors, will not gather firewood along roads constructed by operators. If wood cutting is required, a permit will be obtained from the Forestry Department of the BIA pursuant to 25 CFR 169.13 "Assessed Damages Incident to Right-of-Way Authorization". All operators, subcontractors, vendors and their employees or agents may not disturb salable timber (including firewood) without a duly granted wood permit from the BIA Forester.

If the surface rights are owned by the Ute Indian Tribe and mineral rights are owned by another entity, an approved rights-of-way will be obtained from the BIA before the operator begins any construction activities. If the surface is owned by another entity and the mineral rights are owned by the Ute Indian Tribe, rights-of-way will be obtained from the other entity.

All roads constructed by operators on the Uinta and Ouray Indian Reservation will have appropriate signs. Signs will be neat and of sound construction. They will state: (a) that the land is owned by the Ute Indian Tribe, (b) the name of the operator, (c) that firearms are prohibited to all non-Ute Tribal members, (d) that permits must be obtained from the BIA before cutting firewood or other timber products and (e) only authorized personnel permitted.

CONFIDENTIAL

All well site locations on the Uinta and Ouray Indian Reservation will have an appropriate sign indicating the name of the operator, the lease serial number, the well name and number, the survey description of the well (either footages or the quarter-quarter section, the section, township, and range).

Additional Surface Stipulations

- ___ No construction or drilling activities shall be conducted between _____ and _____ because of _____

- ___ No surface occupancy will be allowed within 1,000 feet of any sage grouse strutting ground.
- ___ No construction or exploration activities are permitted within 1.5 mile radius of sage grouse strutting grounds from April 1 to June 30.
- ___ There shall be no surface disturbance within 600 feet of live water (includes stock tanks, springs, and guzzlers).
- ___ No cottonwood trees will be removed or damaged.
- X A silt catchment dam and basin will be constructed according to BLM specifications approximately 300 yds. northwest of the location, where flagged.
- ___ _____

13. Lessee's or Operators Representative and Certification

Representative

Name: _____

Address: _____

Phone No: _____

CONFIDENTIAL

All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, Onshore Oil and Gas Orders, the approved plan of operations, and any applicable Notice to Lessees. The operator is fully responsible for the actions of his subcontractors. A copy of these conditions will be furnished the field representative to insure compliance.

A complete copy of the approved APD and ROW grant, if applicable, shall be on location during construction of the location and drilling activities.

The operator or his/her contractor shall contact the BLM Office at (801) 789-1362 forty-eight (48) hours prior to construction activities.

The BLM Office shall be notified upon site completion prior to moving on the drilling rig.

Certification:

I hereby certify that I, or persons under my direct supervision, have inspected the proposed drillsite and access route; that I am familiar with the conditions which currently exist; that the statements made in this plan are true and correct to the best of my knowledge; and, that the work associated with the operations proposed here will be performed by CNG Producing Company and its contractors and subcontractors in conformity with this plan and the terms and conditions under which it is approved. This statement is subject to the provisions of 18 U.S.C. 1001 for the filing of a false statement.



<u>May 5, 1992</u>	<u>David L. Linger</u>
Date	Senior Drilling Engineer
	Name and Title

Onsite Date: May 4, 1992

Participants on Joint Inspection

<u>Greg Darlington</u>	<u>Environmental Tech</u>
<u>Karl Wright</u>	<u>Water Shed Specialist</u>
<u>Darwin Kulland</u>	<u>Manager Production - CNG</u>
<u>Jim Jackson</u>	<u>Drilling Consultant</u>

CNG PRODUCING CO
WELL LAYOUT PLAT
RBU 13-17F



APPROXIMATE QUANTITIES

CUT: 9500 yds (includes pit)
FILL: 2000 yds

JERRY D. ALLRED & ASSOCIATES
Surveying & Engineering Consultants

127 North Center Street
P.O. Drawer C
CLOCHESNE UTAH 84021
(801) 738-5352


2 May '92 79-128-242

CNG

PRODUCING
COMPANY

LEGEND

D = Oil Line
G = Gas Line
W = Water Line
R = Relief Line (Pressure)
C = Condensate Line
V = Vent Line
D = Drain Line
M = Gas Meter
P = Pump
BP = Back Pressure Valve
SWS = Sealed When Shipping
SUS = Sealed Unless Shipping
T = Heat Traced Line
H = Heater
BL = Buried Line
X = Valve
↗ = Check Valve
SC = Sealed Closed Valve
NC = Normally Closed
BD = Blowdown Line



The site security plan is on file in CNGP's district office located at 1400 N. State St., Roosevelt, Utah. It can be inspected during office hours, from 6:30 AM thru 3:30 PM, Monday thru Friday..

CNG PRODUCING COMPANY

Well: RBU 13-17F


RIVER BEND FIELD, UINTA COUNTY


not to scale

SDR\ RBU\ FLOW1 SEP

TYPICAL FLOW DIAGRAM

date: 5/5/92





CNG PRODUCING COMPANY
RIVER BEND UNIT
UTAH COUNTY, UTAH
1992 DRILLING PROGRAM
PARTICIPATING AREAS LAND PLAT
Revised 9-24-91
7-22-91 CNS

NOTE:—The information on the following blanks should be true from examination of records, but when necessary, a complete supplementary statement should be made on the following page under the heading "Explanatory."

For the purpose of acquiring the right to use a portion of the unappropriated water of the State of Utah, for uses indicated by (X) in the proper box or boxes, application is hereby made to the State Engineer, based upon the following showing of facts, submitted in accordance with the requirements of the Laws of Utah.

1. Irrigation ☐ Domestic ☐ Stockwatering ☐ Municipal ☐ Power ☐ Mining ☐ Other Uses ☒
2. The name of the applicant is MAPCO, Inc. Production Co.
3. The Post Office address of the applicant is P.O. Box 1360, Bountiful, Utah 84065
4. The quantity of water to be appropriated 0.15 second-feet and/or acre-feet
5. The water is to be used for Oil Well Drilling from January 1 to December 1
(Major Purpose) (Month) (Day) (Month) (Day)
other use period _____ from _____ to _____
(Minor Purpose) (Month) (Day) (Month) (Day)
and stored each year (if stored) from January 1 to December 1
(Month) (Day) (Month) (Day)

6. The drainage area to which the direct source of supply belongs is _____ (Leave blank)

7. The direct source of supply is* Underground water from Green River Formation
(Name of stream or other source)
which is tributary to _____ tributary to _____

*Note.—Where water is to be diverted from a well, a tunnel, or drain, the source should be designated as "Underground Water" in the first space and the remaining spaces should be left blank. If the source is a stream, a spring, a spring area, or a drain, so indicate in the first space, giving its name, if named, and in the remaining spaces, designate the stream channels to which it is tributary, even though the water may sink, evaporate, or be diverted before reaching said channels. If water from a spring flows in a natural surface channel before being diverted, the direct source should be designated as a stream and not a spring.

8. The point of diversion from the source is in Utah County, situated at a point*
Center SE of NE Section 17 T10 S R20 E
3. 1900' W. 1/4 Sec. 17 T10 S R20 E
8 miles S. 0000'

*Note.—The point of diversion must be located definitely by course and distance or by giving the distances north or south, and east or west with reference to a United States land survey corner or United States mineral monument, if within a distance of six miles of either, or if at a greater distance, to some prominent and permanent natural object. No application will be received for filing in which the point of diversion is not defined definitely.

9. The diverting and carrying works will consist of A 7 5/8" well and 2500' deep

10. If water is to be stored, give capacity of reservoir in acre-feet 1 height of dam 5
area inundated in acres 1/4 legal subdivision of area inundated SE of NW
Sec 17 T10 S R20 E

11. If application is for irrigation purposes, the legal subdivisions of the area irrigated are as follows:

12. Is the land owned by the applicant? Yes _____ No X Total _____ Acres

13. Is this water to be used supplementally with other water rights? Yes _____ No X
If "yes," identify other water rights on page 2.

14. If application is for power purposes, describe type of plant, size and rated capacity.

15. If application is for mining, the water will be used in _____ Mining District at the _____ mine, where the following ores are mined _____

16. If application is for stockwatering purposes, number and kind of stock watered 1000 head of Sheep

17. If application is for domestic purposes, number of persons _____ or families _____

18. If application is for municipal purposes, name of municipality _____

19. If application is for other uses, include general description of proposed uses Drilling Riverbend Unit well by MAPCO. T9 + 10 S R19 + 20 E

20. Give place of use by legal subdivision of the United States Land Survey for all uses described in paragraphs 14 to 19, incl. _____

21. The use of water as set forth in this application will consume 0.015 second feet and/or acre-feet of water and 0.015 second feet and/or acre feet will be returned to the natural stream or source at a point described as follows: _____

The land is leased to the Federal Government and is situated by the Bureau of Land Management and has their approval.

The B.L.M. will use the excess water for wild life + stock watering

(Use page 4 if additional explanatory is needed.)

The quantity of water sought to be appropriated is limited to that which can be beneficially used for the purpose herein described

Darwin Kulland Jan 1972
Signature of Applicant

"If applicant is a corporation or other organization, signature must be the name of such corporation or organization by its proper officer, or in the name of the partnership by one of the partners, and the names of the other partners shall be listed. If a corporation or partnership, the affidavit below need not be filled in. If there is more than one applicant, a power of attorney, authorizing one to act for all, should accompany the Application.

DECLARATION OF CITIZENSHIP

STATE OF UTAH.

County of Wasatch

On the 16 day of June 1972, personally appeared before me, a notary public for the State of Utah, the above applicant who, on oath, declared that he is a citizen of the United States, or has declared his intention to become such a citizen.

My commission expires:

Aug 7, 1982

(SEAL)

[Signature]
Notary Public

SELF-CERTIFICATION STATEMENT


Self-certification statement. Under the Federal regulation in effect as of June 15, 1988 designation of operator forms are no longer required when the operator is not the 100% record title holder. An operator is now required to submit a self-certification statement to the appropriate Bureau office stating that said operator has the right to operate upon the leasehold premises. Said notification may be in the following format:

"Please be advised that CNG Producing Company is considered to be the operator of Well No. 13-17F SW 1/4 of SW 1/4 Section 17, Township 10, Range 20; Lease U-013769-C Uintah County, Utah; and is responsible under the terms and conditions of the lease for the operations conducted upon the leased lands. Bond coverage is provided by American Casualty Company of Reading, PA, Bond #524 7050.


RS Gloger
R. S. Gloger
Drilling Manager

CONFIDENTIAL

BOP STACK



CHOKER MANIFOLD



CONTINUED

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

APPLICATION FOR PERMIT TO DRILL, DEEPEN, OR PLUG BACK

1a. TYPE OF WORK

DRILL ☒ DEEPEN ☐ PLUG BACK ☐

b. TYPE OF WELL

OIL WELL ☐ GAS WELL ☒ OTHER ☐ SINGLE ZONE ☐ MULTIPLE ZONE ☐

2. NAME OF OPERATOR

CNG PRODUCING COMPANY

3. ADDRESS OF OPERATOR

CNG Tower, 1450 Poydras St., New Orleans, LA 70112-6000

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.)*

At surface

646' FWL & 690' FSL

At proposed prod. zone

Same

14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE*

10 Miles SW of Ouray

15. DISTANCE FROM PROPOSED*

LOCATION TO NEAREST
PROPERTY OR LEASE LINE, FT.

(Also to nearest drlg. unit line if any) 4,590'

16. NO. OF ACRES IN LEASE

600

17. NO. OF ACRES ASSIGNED
TO THIS WELL

80

18. DISTANCE FROM PROPOSED LOCATION*

TO NEAREST WELL, DRILLING, COMPLETED,
OR APPLIED FOR, ON THIS LEASE, 1,760'

19. PROPOSED DEPTH

7,600' DSTC

20. ROTARY OR CABLE TOOLS

Rotary

21. ELEVATIONS (Show whether DF, RT, GR, etc.)

5,149' GR

22. APPROX. DATE WORK WILL START

June, 1992

23.

PROPOSED CASING AND CEMENTING PROGRAM

SIZE OF HOLE	SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH	QUANTITY OF CEMENT
12 1/4"	8 5/8"	24#	+/- 350	Cement to Surface
7 7/8"	5 1/2"	17#	+/- 7,600	Cement Calc to Surface

1. Drill a 12 1/4" hole with an air rig to +/- 350', run 8 5/8", H-40 casing and cement to surface.
2. NU and pressure test BOP stack prior to drilling out below surface pipe.
3. Operate pipe rams daily and blind rams as possible.
4. Drill a 7 7/8" hole to 7,600' with a salt water mud system. Coring is possible. DST's will be run as needed to evaluate unexpected shows.
5. Run logs, set 5 1/2", 17#, N 80 & K-55 casing as dictated by drilling shows, tests, and logs. Casing program may be modified to provide added burst strength if needed for frac program.
6. Primary zones of interest are the Wasatch, Chapita Wells & Ute Land Buttes.
7. All zones indicating potential for economically recoverable reserves will be tested in a normal, prudent manner.
8. In the event of lost circulation, air or air assisted mud will be utilized.

FORMATION TOPS

DEPTHS

Wasatch 4,650'
Chapita Wells 5,390'
Ute Land Buttes 6,400'

CNG Producing respectfully request that all information concerning this well be held confidential.

IN ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen or plug back, give data on present productive zone and proposed new productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface geology and maximum depth. Give blowout preventer program, if any.

24. SIGNED David L. Linger
David L. Linger

TITLE Senior Drilling Engineer

DATE: 5-11-92

BY: [Signature]

WELL SPACING: 49-2-3

(This space for Federal or State office use)

PERMIT NO. 13-047-302041

APPROVAL DATE

APPROVED BY

TITLE

CONDITIONS OF APPROVAL, IF ANY:


*See Instructions On Reverse Side

OPERATOR CNG Petroleum Co N-0605 DATE 3-11-90
WELL NAME RBD 13-17F
SEC S4SW17 T 10S R 00E COUNTY Wirtah


43-047-30041
API NUMBER

Lease (1)
TYPE OF LEASE

CHECK OFF:



PLAT.



BOND



NEAREST
WELL



LEASE



FIELD



POTASH OR
SODIUM

CONFIDENTIAL

PROCESSING COMMENTS:

Included in amended 90-POD approved 4-09-90.

Water Permit

Oil shale area

APPROVAL LETTER:

SPACING:



R649-2-3


R615-2-3

Revised Bond

UNIT



R615-3-2



N/A

CAUSE NO. & DATE



R615-3-3

STIPULATIONS:

1- Oil shale area

CONFIDENTIAL

PERIOD

EXPIRED

ON 9-16-93



Norman H. Bangerter
Governor

Dee C. Hansen
Executive Director

Dianne R. Nielson, Ph.D.
Division Director

State of Utah

DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

355 West North Temple
3 Triad Center, Suite 350
Salt Lake City, Utah 84180-1203
801-538-5340

May 11, 1992

CNG Producing Company
CNG Tower, 1450 Poydras Street
New Orleans, Louisiana 70112-6000

Gentlemen:

Re: RBU 13-17F Well, 690 feet from the south line, 646 feet from the west line, SW 1/4 SW 1/4, Section 17, Township 10 South, Range 20 East, Uintah County, Utah

Pursuant to Utah Code Ann. § 40-6-18, (1953, as amended), Utah Admin. R. 649-2-3, and Utah R. 649-3-4, approval to drill the referenced well is hereby granted.

In addition, the following specific actions are necessary to fully comply with this approval:

1. Compliance with the requirements of Utah Admin. R. 649-1 et seq., Oil and Gas Conservation General Rules.
2. Notification within 24 hours after drilling operations commence.
3. Submittal of Entity Action Form, Form 6, within five working days following commencement of drilling operations and whenever a change in operations or interests necessitates an entity status change.
4. Submittal of the Report of Water Encountered During Drilling, Form 7.
5. Prompt notification prior to commencing operations, if necessary, to plug and abandon the well. Notify Frank R. Matthews, Petroleum Engineer, (Office) (801)538-5340, (Home) (801)476-8613, or R.J. Firth, Associate Director, (Home) (801)571-6068.
6. Compliance with the requirements of Utah Admin. R. 649-3-20, Gas Flaring or Venting, if the well is completed for production.

Page 2
CNG Producing Company
RBU 13-17F Well
May 11, 1992

Prior to commencement of the proposed drilling operations, plans for facilities for disposal of sanitary wastes at the drill site should be submitted to the local health department. These drilling operations and any subsequent well operations should be conducted in accordance with applicable state and local health department regulations. A list of local health departments and copies of applicable regulations are available from the Department of Environmental Quality, Division of Drinking Water/Sanitation, telephone (801)538-6159.

This approval shall expire one year after date of issuance unless substantial and continuous operation is underway or a request for an extension is made prior to the approval expiration date. The API number assigned to this well is 43-047-32241.

Sincerely,

A handwritten signature in black ink, appearing to read 'R.J. Firth', is written over a rectangular stamp area.

R.J. Firth
Associate Director, Oil and Gas

ldc
Enclosures
cc: Bureau of Land Management
J.L. Thompson
WO11

A Class III Cultural Resource Inventory of
Consolidated Natural Gas Co. Proposed Well Location
RBU-13-17F, Access and Pipeline.

g.b.p. 7/2/92

By
James A. Truesdale

Michael D. Metcalf
Principal Investigator

Prepared By
Metcalf Archaeological Consultants, Inc.
P.O.Box 899
Eagle, Colorado
81631

Utah Project #
U-92-MM-280 (b)

June, 1992

Introduction

Metcalf Archaeological Consultants, Inc. (MAC) was contacted by Darwin Kulland a representative for CNG Producing Company to conduct a Class III cultural resource survey and inventory of proposed well location RBU-13-17F (Figure 1). In addition, an access right-of-way and pipeline corridor was also surveyed. The project is located within the original exterior boundaries of the Uintah-Ouray Ute Indian Reservation in Uintah County, Utah but is administered by the Bureau of Land Management, Vernal Office. Legal locations for the project area are Township 10 South, Range 20 East, SW/SW of section 17 (Figure 1). A total area of 10.5 acres of land was surveyed for cultural resources. Fieldwork was completed by James A. Truesdale (MAC Archaeologist) on June 18, 1992.


File Search

A file search was conducted on June 18, 1992 by the Utah State Historical Society, Division of Antiquities and Records. No cultural resources were previously recorded on/or adjacent to the project area surveyed.

Environment

The project area is located physiographically in the Uinta Basin, south of the town of Ouray, Utah. The project area is located in the Wild Horse Bench area and situated within the original exterior boundaries of the Uintah-Ouray Ute Reservation. The project area can generally be characterized as an elevated bench with deflated areas of Uinta Formation (Eocene age) sediments. Sandstone capped benches, ridges and buttes dominate the landscape with deflated desert pavement between. Sediments in the area consist primarily of aeolian sand deposits covering the desert pavement, colluvial deposits along the talus slopes of the hills, and alluvial deposits along the major drainages. The Green River, Hill and Willow Creeks drain the project area. Elevation of the project area is 5240 feet AMSL.

Vegetation in the project area is characteristic of a shadscale/greasewood community with low sagebrush communities found in isolated areas. In addition a riparian community may be found along the Green River which is located approximately seven miles to the west and Willow Creek two miles to the northeast. Species observed in the project area consist of Atriplex confertifolia (shadscale), Atriplex nuttallii (saltbrush), Chrysothamnus viscidiflorus (rabbitbrush), Gutierrezia sarothrae (snakeweed), Ephedra nevadensis (Mormon tea), Eurotia lanata (winterfat), Sarcobatus baileyi (greasewood), Machaeranthera glabriuscula spp (aster), Castilleja spp. (Indian paint brush), Opuntia spp. (prickly pear cactus), Sphaeralcea spp. (globemallow), Bomus tectorum (cheat grass), Oryzopsis hymenoides (Indian rice-grass), Sitanion hystrix (squirreltail grass), Halogeton glomeratus (halogeton), Lepidium perfoliatum (pepper-grass), Oenothera spp. (Russian thistle), Eriogonum spp. (Buckwheat), Eriogonum inflatum (Indianpipe Weed, and (Artemisia spp.) sagebrush.



Field Methodology

The ten acre block survey consisted of walking parallel transects spaced no more than 15 to 20 meters apart. A 100 foot corridor was inventoried for the proposed access road and pipeline. This coverage was obtained by using two zig-zag transects, one on each side of the proposed centerlines. Areas of subsurface sediment exposure (cutbanks, rodent burrows, eroding slopes, ant hills) were examined with special care in order to help assess the potential for buried cultural deposits. All field notes, maps, and a copy of this report are located in the MAC office in Eagle, Colorado.

Results

A Class III cultural resource inventory of the proposed CNG well RBU-13-17F its access and pipeline were conducted by Metcalf Archaeology on June 18, 1992. The well location is situated on the northwest slope and hillside of a sandstone capped Uinta Formation outcrop. On the northwestern side of the sandstone capped ridges are several small sand dunes. The access road runs approximately 200 feet to the northwest to tie into an existing gas field road. This route crosses desert pavement armored with residual pieces of angular sandstone. Sediments on the well location are limited and consist of a desert pavement with residual angular pieces of sandstone. However, several sand dunes are located just outside the ten acre block and may contain a meter or more of aeolian deposits. The proposed well location has little to no sediments. No cultural materials were located on the proposed well location.

Recommendation

Clearance is recommended for the construction of the access road, pipeline and well location RBU-15-17F.

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

APPLICATION FOR PERMIT TO DRILL, DEEPEN, OR PLUG BACK

1a. TYPE OF WORK
DRILL ☒ DEEPEN ☐ PLUG BACK ☐

b. TYPE OF WELL
OIL WELL ☐ GAS WELL ☒ OTHER ☐ SINGLE ZONE ☐ MULTIPLE ZONE ☐

2. NAME OF OPERATOR
CNG PRODUCING COMPANY

3. ADDRESS OF OPERATOR
CNG Tower, 1450 Poydras St., New Orleans, LA 70112-5000

4. LOCATION OF WELL (Report location clearly and in accordance with BLM Manual 100-10.1)
At surface
646' FWL & 690' FSL
At proposed prod. zone
Same

5. LEASE DESIGNATION AND SERIAL NO.
U-013769-G

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

7. UNIT AGREEMENT NAME
River Bend Unit

8. FARM OR LEASE NAME
RBU

9. WELL NO.
13-17F

10. FIELD AND POOL, OR WILDCAT

11. SEC., T., R., M., OR BLK.
AND SURVEY OR AREA
17-T10S-R20E

12. COUNTY OR PARISH
Uintah

13. STATE
Utah

14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE
10 Miles SW of Ouray

15. DISTANCE FROM PROPOSED*
LOCATION TO NEAREST
PROPERTY OR LEASE LINE, FT.
(Also to nearest drlg. unit line if any) 4,590'

16. NO. OF ACRES IN LEASE 600

17. NO. OF ACRES ASSIGNED
TO THIS WELL 80

18. DISTANCE FROM PROPOSED LOCATION*
TO NEAREST WELL, DRILLING, COMPLETED,
OR APPLIED FOR, ON THIS LEASE, 1,760'

19. PROPOSED DEPTH 7,600'

20. ROTARY OR CABLE TOOLS
Rotary

21. ELEVATIONS (Show whether DF, RT, GR, etc.)
5,149' GR

22. APPROX. DATE WORK WILL START
June, 1992

23. PROPOSED CASING AND CEMENTING PROGRAM				
SIZE OF HOLE	SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH	QUANTITY OF CEMENT
12 1/4"	8 5/8"	24#	+/- 350	Cement to Surface
7 7/8"	5 1/2"	17#	+/- 7,600	Cement Calc to Surface

1. Drill a 12 1/4" hole with an air rig to +/- 350', run 8 5/8", H-40 casing and cement to surface.
2. NU and pressure test BOP stack prior to drilling out below surface pipe.
3. Operate pipe rams daily and blind rams as possible.
4. Drill a 7 7/8" hole to 7,600' with a salt water mud system. Coring is possible. DST's will be run as needed to evaluate unexpected shows.
5. Run logs, set 5 1/2", 17#, N 80 & K-55 casing as dictated by drilling shows, tests, and logs. Casing program may be modified to provide added burst strength if needed for frac program.
6. Primary zones of interest are the Wasatch, Chapita Wells & Ute land Buttes.
7. All zones indicating potential for economically recoverable reserves will be tested in a normal, prudent manner.
8. In the event of lost circulation, air or air assisted mud will be utilized.

FORMATION TOPS	DEPTHS
Wasatch	4,650'
Chapita Wells	5,390'
Ute land Buttes	6,400'

CONFIDENTIAL

CNG Producing respectfully request that all information concerning this well be held confidential.

IN ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen or plug back, give data on present productive zone and proposed new productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depth. Give blowout preventer program, if any.

SIGNED David L. Linger
David L. Linger

TITLE Senior Drilling Engineer

DATE 05/05/92

(This space for Federal or State office use)

PERMIT NO.

APPROVAL DATE

ASSISTANT DISTRICT

APPROVED BY Thomas B. Linger

TITLE

MANAGER

DATE JUL 7 1992

CONDITIONS OF APPROVAL, IF ANY:

NOTICE OF APPROVAL

UT 080-2M-145

*See Instructions On Reverse Side

CONDITIONS OF APPROVAL ATTACHED

RECEIVED

JUL 08 1992

CONDITIONS OF APPROVAL FOR NOTICE TO DRILL

DIVISION OF
OIL GAS & MINING

Company CNG Producing Company

Well No. RBU 13-17F

Location SWSW, Section 17, T10S, R20E

Lease No. U - 013769 - C

Approval of this application does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Be aware fire restrictions may be in effect when location is being constructed and/or when well is being drilled. Contact the appropriate Surface Management Agency for information.

A. DRILLING PROGRAM

1. Estimated Depth at Which Oil, Gas, Water, or Other Mineral Bearing Zones are Expected to be Encountered

Report ALL water shows and water-bearing sands to Tim Ingwell of this office. Copies of State of Utah form OGC-8-X are acceptable. If noticeable water flows are detected, submit samples to this office along with any water analyses conducted.

All usable water and prospectively valuable minerals (as described by BLM at onsite) encountered during drilling, will be recorded by depth and adequately protected. All oil and gas shows will be tested to determine commercial potential.

2. Pressure Control Equipment

The BOP and related equipment shall meet the minimum requirements of onshore Oil and Gas Order No. 2 for equipment and testing requirements, procedures, etc., and individual components shall be operable as designed. Chart recorders shall be used for all pressure tests.

Test charts, with individual test results identified, shall be maintained on location while drilling and shall be made available to a BLM representative upon request.

The special drilling requirements in Onshore Oil and Gas Order No. 2, regarding air or gas drilling shall be adhered to if air is used as the principle drilling medium, i.e., if the rig mud pumps are not being utilized while drilling.

3. Casing Program and Auxiliary Equipment

Surface casing shall have centralizers on the bottom three joints, with a minimum of one centralizer per joint.

As a minimum, the usable water and oil shale resources shall be isolated and/or protected by having a cement top for the production casing at least 200 ft. above the top of the Mahogany oil shale, identified at \pm 2,020 ft. If gilsonite is encountered while drilling, it shall be isolated and/or protected via the cementing program.

4. Mud Program and Circulating Medium

Hazardous substances specifically listed by the EPA as a hazardous waste or demonstrating a characteristic of a hazardous waste will not be used in drilling, testing, or completion operations.

No chromate additives will be used in the mud system on Federal and Indian lands without prior BLM approval to ensure adequate protection of fresh water aquifers.

5. Coring, Logging and Testing Program

Daily drilling and completion progress reports shall be submitted to this office on a weekly basis.

All Drill Stem tests (DST) shall be accomplished during daylight hours, unless specific approval to start during other hours is obtained from the AO. However, DSTs may be allowed to continue at night if the test was initiated during daylight hours and the rate of flow is stabilized and if adequate lighting is available (i.e., lighting which is adequate for visibility and vapor-proof for safe operations). Packers can be released, but tripping should not begin before daylight unless prior approval is obtained from the AO.

A cement bond log (CBL) shall be utilized to determine the top of cement (TOC) and bond quality for the production casing.

Whether the well is completed as a dry hole or as a producer, "Well Completion and Recompletion Report and Log" (Form 3160-4) will be submitted not later than 30 days after completion of the well or after completion of operations being performed, in accordance with 43 CFR 3164. Two copies of all logs, core descriptions, core analyses, well-test data, geologic summaries, sample description, and all other surveys or data obtained and compiled during the drilling, workover, and/or completion operations, will be filed with Form 3160-4. Samples (cuttings, fluids, and/or gases) will be submitted when requested by the AO.

6. Notifications of Operations

No location will be constructed or moved, no well will be plugged, and no drilling or workover equipment will be removed from a well to be placed in a suspended status without prior approval of the AO. If operations are to be suspended, prior approval of the AO will be obtained and notification given before resumption of operations.

Operator shall report production data to MMS pursuant to 30 CFR 216.5 using form MMS/3160.

Immediate Report: Spills, blowouts, fires, leaks, accidents, or any other unusual occurrences shall be promptly reported in accordance with the requirements of NTL-3A or its revision.

If a replacement rig is contemplated for completion operations, a "Sundry Notice" (Form 3160-5) to that effect will be filed, for prior approval of the AO, and all conditions of this approved plan are applicable during all operations conducted with the replacement rig.

The date on which production is commenced or resumed will be construed for oil wells as the date on which liquid hydrocarbons are first sold or shipped from a temporary storage facility, such as a test tank, and for which a run ticket is required to be generated or, the date on which liquid hydrocarbons are first produced into a permanent storage facility, whichever first occurs; and, for gas wells as the date on which associated liquid hydrocarbons are first sold or shipped from a temporary storage facility, such as a test tank, and for which a run ticket is required to be generated or, the date on which gas is first measured through permanent metering facilities, whichever first occurs.

Should the well be successfully completed for production, the AO will be notified when the well is placed in a producing status. Such notification will be sent by telegram or other written communication, not later than five (5) days following the date on which the well is placed on production.

Gas produced from this well may not be vented or flared beyond an initial authorized test period of 30 days or 50 MMCF following its completion, whichever occurs first, without the prior written approval of the Authorized Officer. Should gas be vented or flared without approval beyond the authorized test period, the operator may be directed to shut-in the well until the gas can be captured or approval to continue venting or flaring as uneconomic is granted and the operator shall be required to compensate the lessor for that portion of the gas vented or flared without approval which is determined to have been avoidably lost.

A schematic facilities diagram as required by 43 CFR 3162.7-2, 3162.7-3, and 3162.7-4 shall be submitted to the appropriate District Office within thirty (30) days of installation or first production, whichever occurs first. All site security regulations as specified in Onshore Oil & Gas Order No. 3 shall be adhered to. All product lines entering and leaving hydrocarbon storage tanks will be effectively sealed in accordance with 43 CFR 3162.7-4.

No well abandonment operations will be commenced without the prior approval of the AO. In the case of newly drilled dry holes or failures, and in emergency situations, oral approval will be obtained from the AO. A "Subsequent Report of Abandonment" Form 3160-5, will be filed with the AO within thirty (30) days following completion of the well for abandonment. This report will indicate where plugs were placed and the current status of surface restoration. Final abandonment will not be approved until the surface reclamation work required by the approved APD or approved abandonment notice has been completed to the satisfaction of the AO or his representative, or the appropriate Surface Managing Agency.

7. Other Information

All loading lines will be placed inside the berm surrounding the tank battery.

All off-lease storage, off-lease measurement, or commingling on-lease or off-lease will have prior written approval from the AO.

Gas meter runs for each well will be located within 500 feet of the wellhead. The gas flowline will be buried or anchored down from the wellhead to the meter and within 500 feet downstream of the meter run or any production facilities. Meter runs will be housed and/or fenced.

The oil and gas measurement facilities will be installed on the well location. The oil and gas meters will be calibrated in place prior to any deliveries. Tests for meter accuracy will be conducted monthly for the first three months on new meter installations and at least quarterly thereafter. The AO will be provided with a date and time for the initial meter calibration and all future meter proving schedules. A copy of the meter calibration reports will be submitted to the Vernal District Office. All meter measurement facilities will conform with Onshore Oil & Gas Order No. 4 for liquid hydrocarbons and Onshore Oil & Gas Order No. 5 for natural gas measurement.

The use of materials under BLM jurisdiction will conform to 43 CFR 3610.2-3.

There will be no deviation from the proposed drilling and/or workover program without prior approval from the AO. Safe drilling and operating practices must be observed. All wells, whether drilling, producing, suspended, or abandoned will be identified in accordance with 43 CFR 3162.

"Sundry Notice and Report on Wells" (Form 3160-5) will be filed for approval for all changes of plans and other operations in accordance with 43 CFR 3162.3-2.

Section 102(b)(3) of the Federal Oil and Gas Royalty Management Act of 1982, as implemented by the applicable provisions of the operating regulations at Title 43 CFR 3162.4-1(c), requires that "not later than the 5th business day after any well begins production on which royalty is due anywhere on a lease site or allocated to a lease site, or resumes production in the case of a well which has been off production for more than 90 days, the operator shall notify the authorized officer by letter or sundry notice, Form 3160-5, or orally to be followed by a letter or sundry notice, of the date on which such production has begun or resumed."

If you fail to comply with this requirement in the manner and time allowed, you shall be liable for a civil penalty of up to \$10,000 per violation for each day such violation continues, not to exceed a maximum of 20 days. See Section 109(c)(3) of the Federal Oil and Gas Royalty Management Act of 1982 and the implementing regulations at Title 43 CFR 3162.4-1(b)(5)(ii).

APD approval is valid for a period of one (1) year from the signature date. An extension period may be granted, if requested, prior to the expiration of the original approval period.

In the event after-hours approvals are necessary, please contact one of the following individuals:

Gerald E. Kenczka	(801) 781-1190
Petroleum Engineer	

Ed Forsman	(801) 789-7077
Petroleum Engineer	

BLM FAX Machine	(801) 789-3634
-----------------	----------------

EPA'S LIST OF NONEXEMPT EXPLORATION AND PRODUCTION WASTES

While the following wastes are nonexempt, they are not necessarily hazardous.

Unused fracturing fluids or acids

Gas plant cooling tower cleaning wastes

Painting wastes

Oil and gas service company wastes, such as empty drums, drum rinsate, vacuum truck rinsate, sandblast media, painting wastes, spend solvents, spilled chemicals, and waste acids

Vacuum truck and drum rinsate from trucks and drums, transporting or containing nonexempt waste

Refinery wastes

Liquid and solid wastes generated by crude oil and tank bottom reclaimers

Used equipment lubrication oils

Waste compressor oil, filters, and blowdown

Used hydraulic fluids

Waste solvents

Waste in transportation pipeline-related pits

Caustic or acid cleaners

Boiler cleaning wastes

Boiler refractory bricks

Incinerator ash

Laboratory wastes

Sanitary wastes

Pesticide wastes

Radioactive tracer wastes

Drums, insulation and miscellaneous solids.

DIVISION OF OIL, GAS AND MINING

SPUDDING INFORMATION

NAME OF COMPANY: CNG 43-047-32241

WELL NAME: RBU 13-17F

Section 17 Township 10S Range 20E County UINTAH

Drilling Contractor CIRCLE L

Rig # 7C

SPUDDED: Date 7/14/92

Time 9:30 AM

How DRY HOLE

CONFIDENTIAL

Drilling will commence

Reported by DeWAYNE W/LEON ROSS

Telephone # 1-722-4469

Date 7/14/92 SIGNED CAK

ENTITY ACTION FORM - FORM 6

ADDRESS CNG Tower

1450 Poydras Street

New Orleans, LA 70112-6000

ACTION CODE	CURRENT ENTITY NO.	NEW ENTITY NO.	API NUMBER	WELL NAME	WELL LOCATION					SPUD DATE	EFFECTIVE DATE
					QQ	SC	TP	RG	COUNTY		
B	99999	07050	43-047-32241	RBU 13-17F	SW SW	17	10S	20E	Uintah	07/16/92	
WELL 1 COMMENTS: This well is located within River Bend Unit on BLM land. Entity added 8-5-92. <i>ja</i>											
WELL 2 COMMENTS:											
WELL 3 COMMENTS:											
WELL 4 COMMENTS:											
WELL 5 COMMENTS											

ACTION CODES (See instruction on back of form)

- A - establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (explain in comments section)

NOTE: Use COMMENT section to explain why each Action Code was selected.

RECEIVED

AUG 03 1992

DIVISION OF
OIL GAS & MINING

Susan M. Hebert
Signature

Regulatory Reports Asst. II
Title

July 29, 1992
Date

Phone No. (504) 593-7260

DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED

BUDGET BUREAU NO. 1004-0135

EFFECTIVE DATES: MARCH 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir. Use "APPLICATION FOR PERMIT - " for such proposals

SUBMIT IN TRIPLICATE

1. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other	7. If Unit or CA, Agreement Designation River Bend Unit
2. Name of Operator CNG PRODUCING COMPANY	8. Well Name and No. 13-17F
3. Address and Telephone No. CNG Tower - 1450 Poydras Street, New Orleans, LA 70112-6000	9. API Well No. 43-047-32241
4. Location of Well (Footage, Sec., T., R., M., or Survey Description) Surface - 646' FWL & 690' FSL of Sec. 17-T10S-R20E	10. Field and Pool, or Exploratory Area Island
	11. County or Parish, State Uintah, Utah

CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Abandonment	<input type="checkbox"/> Change of Plans
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Recompletion	<input type="checkbox"/> New Construction
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Plugging Back	<input type="checkbox"/> Non-Routine Fracturing
	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> Water Shut-Off
	<input type="checkbox"/> Altering Casing	<input type="checkbox"/> Conversion to Injection
	<input checked="" type="checkbox"/> Other - Spud Notice	<input type="checkbox"/> Dispose Water
	(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)	

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to the work.)*

This is to notify you that the RBU 13-17F was spudded by Leon Ross Drilling on July 16, 1992.

They drilled 385' of 12 1/4" hole and ran 9 jts of 8 5/8" 24# H-40 casing, set at 377.71'.

Cemented by Dowell with 224 sks Class "G" cement, 2% S-1, 1/4#/sk D-29. Displaced with water.

RECEIVED

AUG 03 1992

14. I hereby certify that the forgoing is true and correct

DIVISION OF
OIL GAS & MINING

Signed

David L. Linger
David L. Linger

Title

Senior Drilling Engineer

Date

July 29, 1992

(This space for Federal or State office use)

Approved by

Title

Date

Conditions of approval, if any:

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*See Instructions on Reverse Side

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
BUDGET BUREAU NO. 1004-0135
EXPIRES: MARCH 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir. Use "APPLICATION FOR PERMIT" for such proposals.

SUBMIT IN TRIPLICATE

RECEIVED

AUG 03 1992

DIVISION OF
OIL GAS & MINING

1. Type of Well
☐ Oil Well ☒ Gas Well ☐ Other
2. Name of Operator
ONG PRODUCING COMPANY
3. Address and Telephone No.
ONG Tower - 1450 Poydras Street, New Orleans, LA 70112-6000
4. Location of Well (Footage, Sec., T., R., M., or Survey Description)
Surface - 646' FWL & 690' FSL of Sec. 17-T10S-R20E
5. Lease Designation and Serial No.
U-013769-C
6. If Indian, Allottee or Tribe Name
7. If Unit or CA, Agreement Designation
River Bend Unit
8. Well Name and No.
13-17F
9. API Well No.
43-047-32241
10. Field and Pool, or Exploratory Area
Island
11. County or Parish, State
Uintah, Utah

CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

TYPE OF ACTION

☐ Notice of Intent

☒ Subsequent Report

☐ Final Abandonment Notice

☐ Abandonment

☐ Recompletion

☐ Plugging Back

☐ Casing Repair

☐ Altering Casing

☒ Other - Weekly Report

☐ Change of Plans

☐ New Construction

☐ Non-Routine Fracturing

☐ Water Shut-Off

☐ Conversion to Injection

☐ Dispose Water

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measure, and true vertical depths for all markers and zones pertinent to the work.)*

July 28 - July 31, 1992

Test BOPs, pipe rams, blind rams, kelly valve, choke, hydril and casing - tested ok. Pick up bottom hole assembly and drill collars. Drill cement, float and shoe. Resume drilling. Survey at 515'. Drilling. Rig service. Drilling. Survey at 1,011'. Drilling. Survey at 1,516'. Drilling. Survey at 2,032'. Drilling. Survey at 2,530'. Drilling. Rig service. Drilling. Survey at 3,029'. Drilling. Survey at 3,522'. Drilling. Rig service - check pipe rams & hydril. Survey at 4,015'. Drilling. Survey at 4,514'. Drilling. Rig service - check BOPs, change swivel packing. Drilling. Survey at 5,012'. Drilling. Mud wt. 8.5. TD at 5,256'.

14. I hereby certify that the forgoing is true and correct

Signed Susan M. Hebert Title Regulatory Report Asst. II Date July 31, 1992
Susan M. Hebert

(This space for Federal or State office use)

Approved by _____ Title _____ Date _____
Conditions of approval, if any: _____

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*See Instructions on Reverse Side

REPORT OF WATER ENCOUNTER DURING DRILLING - FORM 7 (1/89)

RECEIVED

AUG 03 1992

DIVISION OF
OIL, GAS & MINING

1. Well name and number: RBU 13-17F
API number: 43-047-32241
2. Well location: QQ SW SW section 17 township 10S range 20E county Uintah
3. Well operator: CNG Producing Company
Address: CNG Tower - 1450 Poydras Street phone: (504) 593-7000
New Orleans, LA 70112-6000
4. Drilling contractor: Circle L Drilling
Address: 826 South 1500 East phone: (801) 781-2069
Vernal, UT 64078

5. Water encountered (continue on reverse side if necessary)

Depth		Volume (flow rate or head)	Quality (fresh or salty)
from	to		
2,520'	2,540'	50 BPH	Fresh

6. Formation tops: Wasatch Tongue 4,150'
- _____
- _____
- _____

If an analysis has been made of the water encountered, please attach a copy of the report to this form.

I certify that this report is true and complete to the best of my knowledge.

Name David L. Linger
Title Senior Drilling Engineer

Signature *David L. Linger*
Date July 29, 1992

Comments:

This water flow was encountered while drilling with 272 GPM pump rate and 800 CFM air rate. The approximate fluid weight at the time this water flow was encountered is equal to a 4.5 PPG mud weight equivalent.

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
BUDGET BUREAU NO. 1004-0135
EXPIRES: MARCH 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir. Use "APPLICATION FOR PERMIT - " for such proposals

SUBMIT IN TRIPLICATE

1. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other	7. If Unit or CA, Agreement Designation River Bend Unit
2. Name of Operator CNG PRODUCING COMPANY	8. Well Name and No. 13-17F
3. Address and Telephone No. CNG Tower - 1450 Poydras Street, New Orleans, LA 70112-6000	9. API Well No. 43-047-32241
4. Location of Well (Footage, Sec., T., R., M., or Survey Description) Surface - 646' FWL & 690' FSL of Sec. 17-T10S-R20E	10. Field and Pool, or Exploratory Area Island
	11. County or Parish, State Utah, Utah

CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

☐ Notice of Intent☒ Subsequent Report☐ Final Abandonment Notice

TYPE OF ACTION

☐ Abandonment☐ Recompletion☐ Plugging Back☐ Casing Repair☐ Altering Casing☒ Other - Weekly Report☐ Change of Plans☐ New Construction☐ Non-Routine Fracturing☐ Water Shut-Off☐ Conversion to Injection☐ Dispose Water

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measure and true vertical depths for all markers and zones pertinent to the work.)*

August 1 - August 7, 1992

Drilling. Rig service. Drilling. Trip out of hole for new bit. Trip in hole with bit. Wash to bottom. Drilling. Survey at 5,512'. Drilling. Rig service - check BOPs. Survey at 6,018'. Drilling. Survey at 6,504'. Drilling. Rig service - check BOPs. Drilling. Survey at 7,025'. Drilling. Trip for hole in pipe. Found hole in two joints. 42 stands above drill collars, and 34 stands above drill collars. Horizontal cracks middle of joint. Tool joints caliper 5 3/4". Rig service. Trip in hole. Rotary clutch sheared hub bolts - remove - take into machine shop. Work drill pipe 100' off bottom. Trip out of hole. Wait on rotary clutch. Repair - wait on rotary drive. Install rotary drive. Trip in hole. Wash out bridge (5,832-5,892'). Wash out bridge (6,203-6,330'). Trip in hole with 8 stands. Wash 120' to bottom. Drilling. Circulate and condition hole for logs. Short trip - 20 stands. Wash 100' to bottom. Circulate. Trip out of hole. Rig up loggers. Log with Halliburton - work through bridges. Trip in hole to 7,160'. Attempt to unplug bit. Trip out of hole to unplug bit. Trip in hole. Unplug bottom hole drill collar - 2' rust above float. Trip in hole. Wash 170' to bottom - 60' fill. Circulate and condition to run casing. Lay down drill pipe. Run 170 jts 5 1/2" casing. Wash 150' to bottom. Could not wash past 7,270'. Land casing at 7,270'. Circulate. Cement with Dowell using 6 3/4" sks HiLift, 30% D-44, 10#/sk D42, & 1/4#/sk D-29, 20% D-46 followed by 530 sks 10-0 RFC. Dropped top plug and displaced with 166.6 bbls 20% KCL w/ L-55. Bumped plug with 2500 PSI. 30 bbls cement to surface. Set slips with 140,000 lbs. Nipple down BOPs. TD at 7,300'.

14. I hereby certify that the foregoing is true and correct

Signed Susan M. Hebert Title Regulatory Report Asst. II Date August 7, 1992

Susan M. Hebert

Regulatory Report Asst. II

August 7, 1992

(This space for Federal or State office use)

Approved by _____ Title _____

Conditions of approval, if any: _____ Date _____

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
BUREAU NO. 1004-0138
EXPIRES: MARCH 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir. Use "APPLICATION FOR PERMIT - " for such proposals

SUBMIT IN TRIPLICATE

1. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other	7. If Unit or CA, Agreement Designation River Bend Unit
2. Name of Operator CNG PRODUCING COMPANY	8. Well Name and No. 13-17F
3. Address and Telephone No. CNG Tower - 1450 Poydras Street, New Orleans, LA 70112-6000	9. API Well No. 43-047-32241
4. Location of Well (Footage, Sec., T., R., M., or Survey Description) Surface - 646' FWL & 690' FSL of Sec. 17-T10S-R20E	10. Field and Pool, or Exploratory Area Island
	11. County or Parish, State Uintah, Utah


CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Abandonment	<input type="checkbox"/> Change of Plans
	<input type="checkbox"/> Recompletion	<input type="checkbox"/> New Construction
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Plugging Back	<input type="checkbox"/> Non-Routine Fracturing
	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Altering Casing	<input type="checkbox"/> Conversion to Injection
	<input checked="" type="checkbox"/> Other - Weekly Report	<input type="checkbox"/> Dispose Water
	(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)	

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measure and true vertical depths for all markers and zones pertinent to the work.)*

August 8 - August 14, 1992

Nipple down BOPs. Cut off casing. Clean mud tanks. Release rig on 8/8/92. Rig up BOPs on tubing head and 2" test line to pit on 18/64 choke. Rig up general rig. Rig up Halliburton Logging Service. Ran GR - CCL from 7,148' - 4,500'. Perforated Zone #1 (6,905', 6,900', 6,898', 6,896', 6,888', 6,886', 6,610', 6,608', 6,604', 6,468', 6,466', 6,459', 6,454', 6,332', 6,334', & 6,336'). Rig down Halliburton Logging Service. Trip in hole to 6,917'. Spotted 600 gallons of 15% HCL. Pull out of hole to 6,262'. Nipple down BOPs. Nipple up tree. Rig up Western. Tested lines to 6000 PSI. Broke down perms at 2500 PSI at 4 BPM. Pumped 37 bbls of 15% HCL and 32 balls. Well balled off. Surged same three times. Rig down Western and general rig.



14. I hereby certify that the forgoing is true and correct

Signed Susan M. Hebert Title Regulatory Report Asst. II Date August 14, 1992
Susan M. Hebert

(This space for Federal or State office use)

Approved by _____ Title _____ Date _____
Conditions of approval, if any: _____

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*See Instructions on Reverse Side

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
DGET BUREAU NO. 1004-0135
EXPIRES: MARCH 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a
different reservoir. Use "APPLICATION FOR PERMIT - " for such proposals

SUBMIT IN TRIPLICATE

1. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other	7. If Unit or CA, Agreement Designation River Bend Unit
2. Name of Operator CNG PRODUCING COMPANY	8. Well Name and No. 13-17F
3. Address and Telephone No. CNG Tower - 1450 Poydras Street, New Orleans, LA 70112-6000	9. API Well No. 43-047-32241
4. Location of Well (Footage, Sec., T., R., M., or Survey Description) Surface - 646' FWL & 690' FSL of Sec. 17-T10S-R20E	10. Field and Pool, or Exploratory Area Island
	11. County or Parish, State Uintah, Utah

CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Abandonment	<input type="checkbox"/> Change of Plans
	<input type="checkbox"/> Recompletion	<input type="checkbox"/> New Construction
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Plugging Back	<input type="checkbox"/> Non-Routine Fracturing
	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Altering Casing	<input type="checkbox"/> Conversion to Injection
	<input checked="" type="checkbox"/> Other - Weekly Report	<input type="checkbox"/> Dispose Water
	(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)	

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measure and true vertical depths for all markers and zones pertinent to the work.)*

August 15 - August 21, 1992

Rig up Western. Tested lines to 6500 PSI. Broke down well at 34 BPM with 4500 PSI. Frac'd well with 288,000 lbs of 20/40 frac sand, 1,783 bbls of gelled fluid and 63 tons of CO₂. Ramped sand from 1-10 PPG. Average treating pressure - 4700 PSI. Pressure bled from 2450 PSI - 1900 PSI. Opened well 1 hr later on 18/64 choke with 1850 PSI. Flowing tubing to pit on 18/64 choke with 500 PSI on tubing returning mist of water, would not burn. Flowing tubing to pit on 18/64 choke with 500 PSI on tubing and 700 PSI on casing returning mist of water, wouldn't burn. Flowing tubing to pit on 18/64 choke with 350 PSI on tubing and 450 PSI on casing returning gas at the rate of 750 MCF/D, would burn.

RECEIVED

AUG 24 1992

DIVISION OF
OIL GAS & MINING

14. I hereby certify that the forgoing is true and correct

Signed Susan M. Hebert Title Regulatory Report Asst. II Date August 21, 1992
Susan M. Hebert

(This space for Federal or State office use)

Approved by _____ Title _____ Date _____

Conditions of approval, if any:

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*See Instructions on Reverse Side

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
BLM BUREAU NO. 1004-0135
EXPIRES: MARCH 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir. Use "APPLICATION FOR PERMIT - " for such proposals

SUBMIT IN TRIPLICATE

1. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other	7. If Unit or CA, Agreement Designation River Bend Unit
2. Name of Operator CNG PRODUCING COMPANY	8. Well Name and No. 13-17F
3. Address and Telephone No. CNG Tower - 1450 Poydras Street, New Orleans, LA 70112-6000	9. API Well No. 43-047-32241
4. Location of Well (Footage, Sec., T., R., M., or Survey Description) Surface - 646' FWL & 690' FSL of Sec. 17-T10S-R20E	10. Field and Pool, or Exploratory Area Island
	11. County or Parish, State Uintah, Utah

CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Abandonment	<input type="checkbox"/> Change of Plans
	<input type="checkbox"/> Recompletion	<input type="checkbox"/> New Construction
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Plugging Back	<input type="checkbox"/> Non-Routine Fracturing
	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Altering Casing	<input type="checkbox"/> Conversion to Injection
	<input checked="" type="checkbox"/> Other - Initial Production	<input type="checkbox"/> Dispose Water
	(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)	

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to the work.)*

Well was placed on initial production on February 16, 1993 at 10:50 AM.

Note: Verbal notification of initial production telephoned into BLM by Sue Hebert, CNG. Information given to Sally Gardner, BLM on February 18, 1993, 10:50 AM.

RECEIVED

FEB 22 1993

DIVISION OF
OIL GAS & MINING

14. I hereby certify that the forgoing is true and correct

Signed Susan M. Hebert Title Regulatory Reports Asst. Date February 18, 1993
Susan M. Hebert

(This space for Federal or State office use)

Approved by _____ Title _____ Date _____
Conditions of approval, if any:

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*See Instructions on Reverse Side

**CNG Producing
Company**

A CNG COMPANY

CNG Tower
1450 Poydras Street
New Orleans LA 70112-6000
(504) 593-7000

February 24, 1993

Mr. David Little
District Manager
Dept. of the Interior
Bureau of Land Management
Vernal District Office
170 South 500 East
Vernal, UT 84078

RECEIVED

FEB 26 1993

DIVISION OF
OIL GAS & MINING

RE: Application for Disposal of Produced Water NTL-2B

Dear Mr. Little:

Pursuant to NTL-2B Revised August 1, 1978, CNG Producing Company hereby makes applications under Section 1, Exception No. 4. This request is for a 30' x 30' pit adjacent to gas separator in which production water is collected. The wells make less than five (5) bbls per day. The evaporation rate for the area is four (4) feet per year and the percolation rate of the soil is approximately 1" per day.

Some of the pits are unlined, (except with native clay), when they are not located next to drainage. These pits have also been tested for water loss. The pits that showed water loss are lined with native clay and a .12 mil liner.

<u>Well Name</u>	<u>Lease Number</u>	<u>Well Location</u>	<u>Section, Township & Range</u>
1. RBU 10-2F	ML-10716	NW SE	2-T10S-R20E
2. RBU 3-3E	U-013765	NE NW	3-T10S-R19E
3. RBU 5-3E	U-03505	SW NW	3-T10S-R19E
4. RBU 9-3E	U-035316	NE SE	3-T10S-R19E
5. RBU 3-10EX	U-035316	NE NW	10-T10S-R19E
6. RBU 5-10F	U-7206	SW NW	10-T10S-R20E
7. RBU 7-10E	U-13792	SW NE	10-T10S-R19E
8. RBU 9-10F	U-7206	NE SE	10-T10S-R20E
9. RBU 13-10F	BIA 14-20-H62-2645	SW SW	10-T10S-R20E
10. RBU 2-11F	U-01790	NW NE	11-T10S-R20E
11. RBU 3-11F	U-7206	NE NW	11-T10S-R20E
12. RBU 7-14E	U-013792	SW NE	14-T10S-R19E
13. RBU 9-14F	U-013793-A	NE SE	14-T10S-R20E
14. RBU 11-14F	U-013793-A	NE SW	14-T10S-R20E
15. RBU 13-14F	U-013793	SW SW	14-T10S-R20E
16. RBU 15-14E	U-013792	SW SE	14-T10S-R19E
17. RBU 15-14F	U-013793-A	SW SE	14-T10S-R20E
18. RBU 15-15E	U-013766	SW SE	15-T10S-R19E
19. RBU 3-16F	ML-3393-A	NE NW	16-T10S-R20E
20. RBU 7-16E	ML-13214	SW NE	16-T10S-R19E
21. RBU 13-16E	ML-13214	SW SW	16-T10S-R19E
22. RBU 15-16E	ML-13214	SW SE	16-T10S-R19E
23. RBU 5-17F	U-013769-C	SW NW	17-T10S-R20E
24. RBU 7-17F	U-013769-C	SW NE	17-T10S-R20E
25. RBU 9-17E	U-013766	NE SE	17-T10S-R19E
26. RBU 9-17F	U-013769-C	NE SE	17-T10S-R20E
27. RBU 13-17F	U-013769-C	SW SW	17-T10S-R20E
28. RBU 3-19FX	U-013769-A	NE NW	19-T10S-R20E
29. RBU 5-19F	U-013769-A	SW NW	19-T10S-R20E
30. RBU 3-20F	U-013793-A	NE NW	20-T10S-R20E

43-04732241

Mr. David Little, District Manager
Bureau of Land Management

Page 2
February 24, 1993

<u>Well Name</u>	<u>Lease Number</u>	<u>Well location</u>	<u>Section, Township & Range</u>
31. RBU 15-20F	U-0143520-A	SW SE	20-T10S-R20E
32. RBU 3-21F	U-013793-A	NE NW	21-T10S-R20E
33. RBU 7-21E	U-013766	SW NE	21-T10S-R19E
34. RBU 9-21F	U-014520-A	NE SE	21-T10S-R20E
35. RBU 11-21F	U-0143520-A	NE SW	21-T10S-R20E
36. RBU 13-21F	U-01435	SW SW	21-T10S-R20E
37. RBU 15-21F	U-0143520-A	SW SE	21-T10S-R20E
38. RBU 13-22E	U-013792	SW SW	22-T10S-R19E
39. RBU 14-22F	U-0143519	SE SW	22-T10S-R20E
40. RBU 15-22E	U-013792	SW SE	22-T10S-R19E
41. RBU 2-23F	U-013793-A	NW NE	23-T10S-R20E
42. RBU 4-23F	U-013793-A	NW NE	23-T10S-R20E
43. RBU 5-23E	U-013766	SW NW	23-T10S-R20E
44. RBU 9-24E	U-013794	NE SE	24-T10S-R19E
45. RBU 11-35B	U-017713	NE SW	35-T9S-R19E

Exact location of the pits have been submitted with the site security diagram. All wells are located within the River Bend Unit except for RBU 9-17E, RBU 7-21E, RBU 13-22E, RBU 15-22E, and RBU 11-35B which are located outside the unit.

If you have any questions or need any further information, please feel free to contact either myself at (504) 593-7260 or our project engineer, Scot Childress, at (504) 593-7574. Thank you for your cooperation.

Sincerely,

Susan M. Hebert
Susan M. Hebert
Regulatory Reports Asst. II

Enclosure

cc: ✓ Utah Board of Oil, Gas & Mining
Yvonne Abadie
Scot Childress
Brian Coffin
Darwin Kulland
Jim Nicas
RBU Well files

**UTAH DIVISION OF OIL, GAS AND MINING
EQUIPMENT INVENTORY**

Operator: CNG PRODUCING COMPANY Lease: State: Federal: Y
Indian: Fee:

Well Name: RBU 13-17F API Number: 43-047-32241
Section: 17 Township: 10S Range: 20E County: UINTAH Field:
NATURAL BUTTES
Well Status: PGW Well Type: Oil: Gas: Y

PRODUCTION LEASE EQUIPMENT: Y CENTRAL BATTERY:

Y Well head Boiler(s) Compressor Separator(s)
Y Dehydrator(s) (1) Shed(s) Line Heater(s) Y Heated
Separator
 VRU Heater Treater(s)

PUMPS:
 Triplex Y Chemical Centrifugal

LIFT METHOD:
 Pumpjack Hydraulic Submersible Flowing

GAS EQUIPMENT:

Y Gas Meters Purchase Meter Y Sales Meter

TANKS:	NUMBER	SIZE
	<u> </u> Oil Storage Tank(s)	<u> </u> BBLs
	<u> </u> Water Tank(s)	<u> </u> BBLs
	<u> </u> Power Water Tank	<u> </u> BBLs
	<u>YES</u> Condensate Tank(s)	<u>1-300 BARREL</u> BBLs
	<u> </u> Propane Tank	<u> </u>

REMARKS: HEATED SEPARATOR, DEHYDRATOR, SALES METER IN SINGLE SHED.

Location central battery: Qtr/Qtr: Section: Township:
Range:

Inspector: DENNIS INGRAM Date: 7/8/93

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

SUBMIT IN DUPLICATE

(See other in-
structions on
reverse side)

Form approved.
Budget Bureau No. 1004-0137
Expires August 31, 1985

WELL COMPLETION OR RECOMPLETION REPORT AND LOG*

1a. TYPE OF WELL: OIL WELL ☐ GAS WELL ☒ DRY ☐ Other ☐

1b. TYPE OF COMPLETION: NEW WORK DEEP- PLUG DIFF. WELL ☒ OVER ☐ EN ☐ BACK ☐ RESVR. ☐ Other ☐

2. NAME OF OPERATOR
CNG Producing Company

3. ADDRESS OF OPERATOR

CNG Tower - 1450 Poydras St., New Orleans, LA 70112-8000

4. LOCATION OF WELL (Report location clearly and in accordance with any state requirements)

At surface 646' FWL & 690' FSL of Sec. 17-T10S-R20E

At top prod. interval reported below

At total depth

RECEIVED

MAR 04 1993

DIVISION OF

OIL GAS & MINING

14. PERMIT NO.
43-047-32241

DATE SETTING
05/11/92

12. COUNTY OR 13. STATE
PARISH
Uintah Utah

15. DATE
SPUDDED
07/16/92

16. DATE T.D.
REACHED
08/06/92

17. DATE COMF. (Ready to prod.)
08/16/92

18. ELEVATION OF
RKB, RT, GR, ETC.*
5,149' GR

19. ELEV. CASINGHEAD

20. TOTAL DEPTH
MD & TVD
7,300'

21. PLUG, BACK T.D.
MD & TVD
7,148'

22. IF MULTIPLE COMPL.,
HOW MANY*
1 Zone

23. INTERVALS
DRILLED BY
----->

ROTARY CABLE
TOOLS TOOLS
Rotary

24. PRODUCING INTERVAL(S), OF THIS COMPLETION - TOP, BOTTOM, NAME (MD AND TVD)*

6,308-36', 6,452-74', 6,598-6,612', 6,884-6,910' - Wasatch

25. TYPE ELECTRIC AND OTHER LOGS RUN

DLL, Den-Neu, GR, Caliper MKD LOG 9-10-92

27. WAS WELL CORED
No

28. CASING RECORD (Report all strings set in well)

CASING SIZE	WEIGHT, LB/FT.	DEPTH SET (MD)	HOLE SIZE	CEMENTING RECORD	AMOUNT PULLED
8 5/8"	24#	378'	12 1/4"	224 sks Class "G" cement, 2% S-1, 1/4# sk D-29.	
5 1/2"	17# N-80	7,270'		637 sks HiLift, 3% D-44, 10# sk D-42, 1/4# sk D-29 & .2% D- followed by 530 sks 10-0 RFC	

29. LINER RECORD

SIZE	TOP (MD)	BOTTOM (MD)	SACKS CEMENT*	SCREEN (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)
					2 3/8"	6,262'	None

31. PERFORATION RECORD (Interval, size and number)

Zone #1 - 6,332', 6,334', 6,336', 6,454', 6,459', 6,466', 6,468', 6,604', 6,608', 6,610', 6,886', 6,888', 6,896', 6,898', 6,900', & 6,905'

32. ACID, SHOT, FRACTURE, CEMENT SQUEEZE, ETC.

DEPTH INTERVAL (MD) AMOUNT AND KIND OF MATERIAL USED
Zone #1 288,000 lbs of 20/40 Frac Sand

33. PRODUCTION

DATE FIRST PRODUCTION		PRODUCTION MET (Flowing, gas lift, pumping - size and type of pump)				WELL STATUS (Producing or shut-in)	
02/16/93		Flowing				Producing	
DATE OF TEST	HOURS TESTED	CHOKE SIZE	PROD'N FOR TEST PERIOD	OIL-BBL.	GAS-MCF.	WATER-BBL.	GAS-OIL RATIO
02/26/93	24	14/64	----->	-	29	-	-
FLOW. TUBING PRESS.	CASING PRESSURE	CALCULATED 24 HR RATE	OIL-BBL.	GAS-MCF.	WATER-BBL.	OIL GRAVITY-API (CORR.)	
800	800	----->	-	29	-	-	
TEST WITNESSES							

34. DISPOSITION OF GAS (Sold, used for fuel, vented, etc.)
Sold

TEST WITNESSED BY
Mitch Hall

35. LIST OF ATTACHMENTS

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records.

SIGNED W. Scot Childress TITLE Supervisor, Prod. Eng.

DATE March 2, 1993

*(See Instruction and Spaces for Additional Data on Reverse Side)


37. SUMMARY OF POROUS ZONES: (Show all important zones of porosity and contents thereof; cored intervals; and all drill-stem, tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries)

FORMATION	TOP	BOTTOM	DESCRIPTION, CONTENTS, ETC.
Wasatch	6,884'	6,910'	sandstone; wh-gy, vfgr-fgr, sbang-sbrnd, calcareous
Wasatch	6,598'	6,612'	aa
Wasatch	6,452'	6,474'	aa
Wasatch	6,308'	6,336'	aa

38.	GEOLOGICAL MARKERS		
	NAME	TOP	
		MEAS. DEPTH	TRUE VERT. DEPTH
	Wasatch Tongue	4,196'	4,196'
	Green River Tongue	4,526'	4,526'
	Wasatch	4,690'	4,690'
	Chapita Wells	5,410'	5,410'
	Uteland Buttes	6,450'	6,450'

**CNG Producing
Company**

CNG Tower
1450 Poydras Street
New Orleans, LA 70112-6000
(504) 593-7000



A **CNG** COMPANY

March 8, 1996

**Mr. Wayne Bankert
U.S. Dept. of the Interior
Bureau of Land Management
Vernal District Office
170 South 500 East
Vernal, UT 84078**

**RE: Subsequent Report for
Plunger Lift Installations**

Dear Wayne:

Enclosed please find sundry notices for various RBU wells that have just completed plunger lift operations. These sundries are being filed in triplicate.

Should you have any questions, please feel free to contact either myself, at (504) 593-7260, or the our project engineer, Scot Childress at (504) 593-7574.

Sincerely,

Susan H. Sachitana
Susan H. Sachitana
Coordinator, Regulatory Reports

Enclosure

cc: **Frank Matthews - Utah Department of Oil, Gas & Mining**
N. Decker
M. Hall
S. Childress
RBU Well Files

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
BUDGET BUREAU NO. 1004-0135
EXPIRES: MARCH 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir. Use "APPLICATION FOR PERMIT - " for such proposals

SUBMIT IN TRIPLICATE

1. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other	7. If Unit or CA, Agreement Designation River Bend Unit
2. Name of Operator CNG PRODUCING COMPANY	8. Well Name and No. 13-17F
3. Address and Telephone No. CNG Tower - 1450 Poydras Street, New Orleans, LA 70112-6000	9. API Well No. 43-047-32241
4. Location of Well (Footage, Sec., T., R., M., or Survey Description) Surface - 646' FWL & 690' FSL of Sec. 17-T10S-R20E	10. Field and Pool, or Exploratory Area Island
	11. County or Parish, State Uintah, Utah

CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Abandonment	<input type="checkbox"/> Change of Plans
	<input type="checkbox"/> Recompletion	<input type="checkbox"/> New Construction
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Plugging Back	<input type="checkbox"/> Non-Routine Fracturing
	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Altering Casing	<input type="checkbox"/> Conversion to Injection
	<input checked="" type="checkbox"/> Other - Plunger Lift	<input type="checkbox"/> Dispose Water
	(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)	

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to the work.)*

*Installed plunger lift equipment on above well. Well on plunger.

14. I hereby certify that the foregoing is true and correct

Signed Scot Childress Title Supervisor, Production Engineering Date 03/08/96

(This space for Federal or State office use)

Approved by _____ Title _____ Date _____

Conditions of approval, if any:

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*See Instructions on Reverse Side

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0135
EXPIRES: July 31, 1996

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or re-enter an abandoned well. Use form 3160-3 (APD) for such proposals.

SUBMIT IN TRIPLICATE - Other instruction on reverse side


1. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other		5. Lease Serial No. U-013769-C
2. Name of Operator CNG PRODUCING COMPANY		6. If Indian, Allottee or Tribe Name
3a. Address 1450 POYDRAS ST, NEW ORLEANS, LA 70112-6000	3b. Phone No. (include area code) (504) 563-7000	7. If Unit or CA/ Agreement, Name and/or No. RIVERBEND UNIT
4. Location of Well (Footage, Sec., T., R., M., or Survey Description) Surface - 646' FWL & 690' FSL of Sec. 17-10S-R20E		8. Well Name and No. 13-17F
		9. API Well No. 43-047-32241
		10. Field and Pool, or Exploratory Area ISLAND
		11. County or Parish, State UINTAH, UTAH

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input checked="" type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input type="checkbox"/> Other _____
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandonment	<input checked="" type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input checked="" type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation have been completed, and the operator has determined that the site is ready for final inspection.)

CNG Producing Company requests temporary abandonment status on this well. This time is needed for engineers to evaluate the well for additional zones or P&A. Time required is 1 year.



14. I hereby certify that the foregoing is true and correct Name (Printed/Typed) SUSAN H. SACHITANA		Title COORDINATOR, REGULATORY REPORTS
Signature <i>Susan H. Sachitana</i>		Date 970716
THIS SPACE FOR FEDERAL OR STATE OFFICE USE		
Approved by	Title	Date
Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.		Office
Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.		

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0135
EXPIRES: July 31, 1996

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or re-enter an abandoned well. Use form 3160-3 (APD) for such proposals.

SUBMIT IN TRIPLICATE - Other instruction on reverse side


1. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other		5. Lease Serial No. U-013769-C
2. Name of Operator CNG PRODUCING COMPANY		6. If Indian, Allottee or Tribe Name
3a. Address 1450 POYDRAS ST, NEW ORLEANS, LA 70112-6000	3b. Phone No. (include area code) (504) 593-7000	7. If Unit or CA/ Agreement, Name and/or No. RIVERBEND UNIT
4. Location of Well (Footage, Sec., T., R., M., or Survey Description) Surface - 646' FWL & 690' FSL of Sec. 17-10S-R20E		8. Well Name and No. 13-17F
		9. API Well No. 43-047-32241
		10. Field and Pool, or Exploratory Area ISLAND
		11. County or Parish, State UINTAH, UTAH

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other PLUNGER LIFT
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandonment	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation have been completed, and the operator has determined that the site is ready for final inspection.)

Installed plunger lift equipment on above well. Well on plunger as of 1/15/98.



14. I hereby certify that the forgoing is true and correct Name (Printed/Typed) SUSAN H. SACHITANA		Title COORDINATOR, REGULATORY REPORTS
Signature <i>Susan H. Sachitana</i>		Date 980120
THIS SPACE FOR FEDERAL OR STATE OFFICE USE		
Approved by	Title	Date
Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.		Office
Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.		

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

6. Lease Designation and Serial Number
U-013769-C

7. Indian Allottee or Tribe Name

8. Unit or Communization Agreement

River Bend Unit

9. Well Name and Number

RBU 13-17F

10. API Well Number
43-047-32241

11. Field and Pool, or Wildcat
NATURAL BUTTES 630

1. Type of Well

☐ Oil Well ☒ Gas Well ☐ Other (specify)

2. Name of Operator
CNG Producing Company

3. Address of Operator
1450 Poydras St., New Orleans, LA 70112-6000

4. Telephone Number
(504) 593-7260

5. Location of Well

Footage : **646' FWL & 690' FSL**
QQ, SEC., T., R., M.: SW SW 17-T10S-R20E

County : **Uintah**
 State : **UTAH**

CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE REPORT OF OTHER DATA

NOTICE OF INTENT
 (Submit in Duplicate)

<input type="checkbox"/> Abandonment	<input type="checkbox"/> New Construction
<input type="checkbox"/> Casing Repair	<input type="checkbox"/> Pull or Alter Casing
<input type="checkbox"/> Change of Plans	<input type="checkbox"/> Recompletion
<input type="checkbox"/> Conversion to Injection	<input type="checkbox"/> Shoot or Acidize
<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Vent or Flare
<input type="checkbox"/> Multiple Completion	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Other	

Approximate Date Work Will Start

SUBSEQUENT REPORT
 (Submit Original Form Only)

<input type="checkbox"/> Abandonment *	<input type="checkbox"/> New Construction
<input type="checkbox"/> Casing Repair	<input type="checkbox"/> Pull or Alter Casing
<input type="checkbox"/> Change of Plans	<input type="checkbox"/> Shoot or Acidize
<input type="checkbox"/> Conversion to Injection	<input type="checkbox"/> Vent or Flare
<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Other	

Annual Status Report

Date of Work Completion

Report results of Multiple Completions and Recompletions to different reservoirs on WELL COMPLETION OR RECOMPLETION AND LOG form.

* Must be accompanied by a cement verification report.

13. DESCRIBE PROPOSED OR COMPLETION OPERATIONS (Clearly state all pertinent details, and give pertinent dates. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

STATUS OF WELL


Shut-in

EXPLANATION FOR STATUS OF WELL

Uncommercial due to water production.

FUTURE PLANS

Run water log evaluation log to identify interval / perms producing water and evaluate to perform workover.



14. I hereby certify that the foregoing is true and correct

Name & Signature

Ralph Hamrick
 Ralph Hamrick

Title **Production Engineer**

Date

January 20, 1998

(State Use Only)

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new well, deepen existing wells, or to reenter plugged and abandoned wells.

Use APPLICATION FOR PERMIT - for such proposals

6. Lease Designation and Serial Number

U-013769-C

7. Indian Allottee or Tribe Name

8. Unit or Communization Agreement

River Bend Unit

9. Well Name and Number

RBU 13-17F

10. API Well Number

43-047-32241

11. Field and Pool, or Wildcat

NATURAL BUTTES 630

1. Type of Well

☐ Oil Well ☒ Gas Well ☐ Other (specify)

2. Name of Operator

CNG Producing Company

3. Address of Operator

1450 Poydras St., New Orleans, LA 70112-6000

4. Telephone Number

(504) 593-7260

5. Location of Well

Footage : 646' FWL & 690' FSL
QQ, SEC., T., R., M.: SW SW 17-T10S-R20E

County : Uintah

State : UTAH

12. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

NOTICE OF INTENT
(Submit in Duplicate)

SUBSEQUENT REPORT
(Submit Original Form Only)

☐ Abandonment ☐ New Construction
☐ Casing Repair ☐ Pull or Alter Casing
☐ Change of Plans ☐ Recompletion
☐ Conversion to Injection ☐ Shoot or Acidize
☐ Fracture Treat ☐ Vent or Flare
☐ Multiple Completion ☐ Water Shut-Off
☐ Other

☐ Abandonment * ☐ New Construction
☐ Casing Repair ☐ Pull or Alter Casing
☐ Change of Plans ☐ Shoot or Acidize
☐ Conversion to Injection ☐ Vent or Flare
☐ Fracture Treat ☐ Water Shut-Off
☒ Other

Annual Status Report

Approximate Date Work Will Start

Date of Work Completion

Report results of Multiple Completions and Recompletions to different reservoirs on WELL COMPLETION OR RECOMPLETION AND LOG form.

* Must be accompanied by a cement verification report.

13. DESCRIBE PROPOSED OR COMPLETION OPERATIONS (Clearly state all pertinent details, and give pertinent dates. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

STATUS OF WELL


Shut-in

EXPLANATION FOR STATUS OF WELL

Uncommercial due to water production.

FUTURE PLANS

Evaluating recompletion.



14. I hereby certify that the foregoing is true and correct

Name & Signature

Ralph Hamrick
Ralph Hamrick

Title

Production Engineer

Date

February 12, 1999

(State Use Only)

STATE OF UTAH
DIVISION OF OIL, GAS & MINING

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, deepen existing wells or to reenter plugged and abandoned wells.
Use APPLICATION FOR PERMIT TO DRILL OR DEEPEN form for such proposals.

1. Type of Well : OIL <input type="checkbox"/> GAS <input checked="" type="checkbox"/> OTHER:	5. Lease Designation and Serial Number: U-013769-C
2. Name of Operator: CNG PRODUCING COMPANY	6. If Indian, Allottee or Tribe Name:
3. Address and Telephone Number: CNG Tower - 1460 Poydras Street, New Orleans, LA 70112-6000 (504) 593-7260	7. Unit Agreement Name: RIVERBEND UNIT
4. Location of Well Footages: 646' FWL & 690' FSL QQ, Sec. T., R., M.: SW SW of Sec. 17-T10S-R20E	8. Well Name and Number: RBU 13-17F
	9. API Well Number 43-047-32241
	10. Field and Pool, or Wildcat: Natural Buttes 630
	County: UINTAH State: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA	
NOTICE OF INTENT (SUBMIT IN DUPLICATE)	SUBSEQUENT REPORT (Submit Original Form Only)
<input type="checkbox"/> Abandon <input type="checkbox"/> Repair Casing <input type="checkbox"/> Change of Plans <input type="checkbox"/> Convert to Injection <input type="checkbox"/> Fracture Treat or Acidize <input type="checkbox"/> Multiple Completion <input type="checkbox"/> Other	<input type="checkbox"/> Abandon* <input type="checkbox"/> Repair Casing <input type="checkbox"/> Change of Plans <input type="checkbox"/> Convert to Injection <input type="checkbox"/> Fracture Treat or Acidize <input checked="" type="checkbox"/> Other
<input type="checkbox"/> New Construction <input type="checkbox"/> Pull or Alter Casing <input type="checkbox"/> Recomplete <input type="checkbox"/> Reperforate <input type="checkbox"/> Vent or Flare <input type="checkbox"/> Water Shut-Off	<input type="checkbox"/> New Construction <input type="checkbox"/> Pull or Alter Casing <input type="checkbox"/> Reperforate <input type="checkbox"/> Vent or Flare <input type="checkbox"/> Water Shut-Off <u>ANNUAL STATUS REPORT FOR STATE OF UTAH</u>
Approximate date work will start _____	Date of work completion _____ Report results of Multiple Completion and Recompletion to different reservoirs on WELL COMPLETION OR RECOMPLETION REPORT AND LOG form. *Must be accompanied by a cement verification report.

12. DESCRIBE PROPOSED OR COMPLETION OPERATIONS (Clearly State all pertinent details, and give pertinent dates. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

STATUS OF WELL

Shut-in

EXPLANATION FOR STATUS OF WELL

Under evaluation.

FUTURE PLANS

Possible workover or plug and abandonment.

RECEIVED

FEB 15 2000

DIVISION OF
OIL, GAS AND MINING

13. Name & Signature: Susan H. Sachitana Title: Regulatory Reports Administrator Date: February 12, 2000
Susan H. Sachitana

(This space for State use only)

**CNG Producing
Company**

A **CNG** COMPANY

CNG Tower
1450 Poydras Street
New Orleans, LA 70112-6000
(504) 593-7000

February 14, 2000

Mr. Don Staley
Administrative Supervisor, Oil & Gas
Utah Board of Oil Gas & Mining
1594 West North Temple
Suite 1210
Salt Lake City, UT 84114-5801

RE: Annual Status Report of Shut-in, Temporarily-abandoned, and Suspended
Drilling Wells

Dear Mr. Staley:

Enclosed please find Sundry Notices for all of CNG Producing Company wells that are required to be reported annually. These wells are shut-in and are being evaluated.

If you have any questions please feel free to contact me at (504) 593-7260 or our project engineer, Ralph Hamrick, at (281) 873-1562.

Sincerely,



Susan H. Sachitana
Regulatory Reports Administrator

Enclosures

cc: Nelda Decker
Mitch Hall
Ralph Hamrick

RECEIVED

FEB 15 2000

DIVISION OF
OIL, GAS AND MINING



United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office
P.O. Box 45155
Salt Lake City, UT 84145-0155

In Reply Refer To:
3100
U-01470-A et al
(UT-932)

JUN 2 2000

NOTICE

Dominion Exploration & Production, Inc. : Oil and Gas Leases
1450 Poydras Street :
New Orleans, LA 70112-6000 :

Name Change Recognized

Acceptable evidence has been received in this office concerning the change of name of CNG Producing Company to Dominion Exploration & Production, Inc. on Federal oil and gas leases.

The oil and gas lease files identified on the enclosed exhibit have been noted as to the name change. The exhibit was compiled from your list of leases and a list of leases obtained from our automated records system. We have not abstracted the lease files to determine if the entity affected by the name change holds an interest in the leases identified nor have we attempted to identify leases where the entity is the operator on the ground maintaining no vested record title or operating rights interests. We are notifying the Minerals Management Service and all applicable Bureau of Land Management offices of the name change by a copy of this notice. If additional documentation for changes of operator are required by our Field Offices, you will be contacted by them.

The following lease on your list is closed on the records of this office: U-029277.

Due to the name change, the name of the principal on the bond is required to be changed from CNG Producing Company to Dominion Exploration & Production, Inc. on Bond No. 524 7050 (BLM Bond No. WY1898). You may accomplish this name change either by consent of the surety on the original bond or by a rider to the original bond. Otherwise, a replacement bond with the new name should be furnished to the Wyoming State Office.

/s/ Robert Lopez

Robert Lopez
Chief, Branch of
Minerals Adjudication

Enclosure
Exhibit of Leases

RECEIVED

JUN 05 2000

DIVISION OF
OIL, GAS AND MINES

cc: Wyoming State Office
New Mexico State Office
Moab Field Office
Vernal Field Office
MMS—Reference Data Branch, MS 3130, Box 5860, Denver, CO 80217
State of Utah, DOGM, Attn: Jim Thompson (Ste. 1210), Box 145801, SLC, UT 84114-5801
Irene Anderson (UT-932)
Teresa Thompson (UT-931)
LaVerne Steah (UT-942)

Dominion Exploration & Production, Inc.
1450 Poydras Street, New Orleans, LA 70112-6000
Phone: 504-593-7000



June 27, 2000

Mr. Jimmy Thompson
Utah Board of Oil Gas & Mining
1594 West North Temple
Suite 1210
Salt Lake City, UT 84114-5801

RE: Name Change Documentation for CNG Producing Company

Dear Mr. Thompson:

CNG Producing Company has become Dominion Exploration & Production, Inc. effective April 12, 2000. Enclosed please find a sundry regarding the name change with an attached listing of all the permits in the name of CNG Producing Company to be changed to Dominion Exploration & Production, Inc. Also enclosed please find a Form UIC 5 for the Transfer of Authority to Inject for the Federal #1-26B well.

If you have any questions or require any additional information, please contact me at (504) 593-7260.

Sincerely,

DOMINION EXPLORATION & PRODUCTION, INC.

Susan H. Sachitana
Regulatory Reports Administrator

Enclosure

cc: Nelda Decker

RECEIVED

JUN 29 2000

**DIVISION OF
OIL, GAS AND MINING**

STATE OF UTAH
DIVISION OF OIL, GAS & MINING

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, deepen existing wells or to reenter plugged and abandoned wells.
Use APPLICATION FOR PERMIT TO DRILL OR DEEPEN form for such proposals.

1. Type of Well : OIL <input type="checkbox"/> GAS <input type="checkbox"/> OTHER:	5. Lease Designation and Serial Number: VARIOUS
2. Name of Operator: DOMINION EXPLORATION & PRODUCTION, INC.	6. If Indian, Allottee or Tribe Name:
3. Address and Telephone Number: 1460 Poydras Street, New Orleans, LA 70112-6000 (504) 593-7260	7. Unit Agreement Name:
4. Location of Well Footages: QQ, Sec. T., R., M.:	8. Well Name and Number: VARIOUS
	9. API Well Number
	10. Field and Pool, or Wildcat: Natural Buttes 630
	County: UINTAH State: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA	
NOTICE OF INTENT (SUBMIT IN DUPLICATE)	SUBSEQUENT REPORT (Submit Original Form Only)
<input type="checkbox"/> Abandon <input type="checkbox"/> Repair Casing <input type="checkbox"/> Change of Plans <input type="checkbox"/> Convert to Injection <input type="checkbox"/> Fracture Treat or Acidize <input type="checkbox"/> Multiple Completion <input type="checkbox"/> Other	<input type="checkbox"/> Abandon* <input type="checkbox"/> Repair Casing <input type="checkbox"/> Change of Plans <input type="checkbox"/> Convert to Injection <input type="checkbox"/> Fracture Treat or Acidize <input checked="" type="checkbox"/> Other
<input type="checkbox"/> New Construction <input type="checkbox"/> Pull or Alter Casing <input type="checkbox"/> Recomplete <input type="checkbox"/> Reperforate <input type="checkbox"/> Vent or Flare <input type="checkbox"/> Water Shut-Off	<input type="checkbox"/> New Construction <input type="checkbox"/> Pull or Alter Casing <input type="checkbox"/> Reperforate <input type="checkbox"/> Vent or Flare <input type="checkbox"/> Water Shut-Off
Approximate date work will start _____	Date of work completion _____ Report results of Multiple Completion and Recompletion to different reservoirs on WELL COMPLETION OR RECOMPLETION REPORT AND LOG form. *Must be accompanied by a cement verification report.

12. DESCRIBE PROPOSED OR COMPLETION OPERATIONS (Clearly State all pertinent details, and give pertinent dates. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

Please be advised that effective April 12, 2000, CNG Producing Company has changed its name to Dominion Exploration & Production, Inc. and would like to transfer the well permits into the name of Dominion Exploration & Production, Inc. Our new bond has been filed and is pending approval with the State of Utah. The bond number is 76S 63050 361.



John R. Lewis

Sr. Vice-President - CNG Producing Company

RECEIVED

JUN 29 2000

DIVISION OF
OIL, GAS AND MINING

13. Name & Signature:  Title: Sr. Vice-President - Dominion Expl. & Prod., Inc. Date: June 26, 2000

(This space for State use only)



State of Utah
DEPARTMENT OF COMMERCE
Division of Corporations & Commercial Code

**Application To Amend The
CERTIFICATE OF AUTHORITY OR
REGISTRATION of**

CNG Producing Company
Business Entity Name

Delaware
Name of Home State

Check Appropriate Box		
<input checked="" type="checkbox"/>	Foreign Profit Corporation	\$35.00
<input type="checkbox"/>	Foreign Non-Profit Corporation	\$35.00
<input type="checkbox"/>	Foreign Limited Partnership	\$25.00
<input type="checkbox"/>	Foreign Limited Liability Company	\$35.00

I. AMENDING THE BUSINESS NAME

The business name is changed to: Dominion Exploration & Production, Inc.

The corporation shall use as its name in Utah: Dominion Exploration & Production, Inc.

(The corporation shall use its name as set forth on #1, unless this name is not available.)

NOTE: If the business name has changed its name in the home state, a copy of the Certificate of Amendment or a certified copy of the amendment must accompany this application.

Check the following:

- ☒ The name of the corporation is changing its name in Utah to the new name of the corporation in the home state.
☐ The name of the corporation is being changed in Utah to comply with Utah State Insurance Regulations.

II. AMENDING THE DURATION OF THE BUSINESS EXISTENCE

The businesses period of duration is changed to: _____

III. AMENDING THE STATE OR COUNTRY OF INCORPORATION/REGISTRATION

The corporation's state or country of incorporation/registration is changed to: _____

IV. Other: _____

(Limited Partnership changing General Partners, Limited Companies changing Members or Managers, Change of statement who is managing, etc.)
Use an attached sheet if needed.

Under penalties of perjury, I declare this Application to Amend the Certificate of Authority or Registration to be, to the best of my knowledge and belief, true and correct.

Signature

Vice President & Corporate Secretary
Title

April 20, 2000
Date

State of Utah
Department of Commerce
Division of Corporations and Commercial Code

I hereby certify that the foregoing has been filed and approved on this 25 day of April, 2000 in the office of this Division and hereby issue this Certificate thereof.

Examiner

Date



Date:

04/25/2000

Receipt Number: 22156

Amount Paid: \$60.00

STATE OF UTAH
DIVISION OF CORPORATIONS
AND COMMERCIAL CODE
160 East 300 South / Box 146705
Salt Lake City, UT 84114-6705
Service Center: (801) 530-4849

Web Site: <http://www.commerce.state.ut.us>


FILED

APR 25 2000

Well Name	Api Well Code	Operator Name	Production Status	Lease Type
RBU #13-24E	430473208300S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #13-35B	430473209400S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #3-21E	430473209500S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #15-17F	430473210300S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #13-19F	430473210500S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #1-21E	430473210700S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #14-2F	430473210800S1	DOMINION EXPLORATION & PR	PR	STATE
RBU #9-21E	430473212800S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #9-17E	430473212900S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #13-14F	430473213300S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #9-11F	430473213400S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #8-2F	430473213600S1	DOMINION EXPLORATION & PR	PR	STATE
RBU #5-16E	430473213700S1	DOMINION EXPLORATION & PR	PR	STATE
RBU #5-21F	430473213800S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #1-20E	430473214600S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #8-18F	430473214900S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #13-23E	430473215300S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #5-24E	430473215400S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #5-14F	430473215600S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #7-15E	430473216600S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #15-13E	430473216700S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #13-10F	430473218900S1	DOMINION EXPLORATION & PR	PR	BIA
RBU #15-10E	430473219000S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #3-17FX	430473219100S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #13-15E	430473219700S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #7-22E	430473219800S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #5-23E	430473219900S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #13-18F	430473220100S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #15-15E	430473221100S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #5-19F	430473221300S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #9-17F	430473221700S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #7-17F	430473221800S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #15-14E	430473221900S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #5-3E	430473222000S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #15-35B	430473222200S1	DOMINION EXPLORATION & PR	PR	BLM
FEDERAL #11-24B	430473222300S1	DOMINION EXPLORATION & PR	PR	BLM
STATE #9-36A	430473222500	DOMINION EXPLORATION & PR	TA	BLM
RBU #9-3E	430473222800S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #7-14E	430473223900S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #9-14F	430473224000S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #13-17F	430473224100S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #5-22E	430473224200S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #15-17E	430473224300	DOMINION EXPLORATION & PR	PA	BLM
RBU #7-16E	430473224500S1	DOMINION EXPLORATION & PR	PR	BLM
FEDERAL #1-26B - GIW	4304732248	DOMINION EXPLORATION & PR	PR	BLM
RBU #13-16E	430473225000S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #8-13E	430473226300S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #9-21F	430473226600S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #5-10F	430473226700S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #9-10F	430473226800S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #14-22F	430473227000S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #9-34B	430473227400S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #5-21E	430473227600S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #7-10E	430473228900S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #5-17F	430473229000S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #15-16E	430473229200S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #3-3E	430473229300S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #13-22E	430473229500S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #7-21E	430473230100S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #15-21F	430473230900S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #15-20F	430473231000S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #9-24E	430473231200S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #3-20F	430473231300S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #10-2F	430473231400S1	DOMINION EXPLORATION & PR	PR	BLM

OPERATOR CHANGE WORKSHEET

Check each listed item when completed. Write N/A if item is not applicable.

	4-KAS ✓
2-CDW ✓	5-SP ✓
3-JLT	6-FILE

Change of Operator (Well Sold)

Designation of Agent

X Operator Name Change Only

Merger

The operator of the well(s) listed below has changed, effective: 4-12-00TO:(New Operator) DOMINION EXPL & PROD INC.FROM:(Old Operator) CNG PRODUCING COMPANYAddress: 1450 POYDRAS STREET
NEW ORLEANS, LA 70112-6000Address: 1450 POYDRAS STREET
NEW ORLEANS, LA 70112-6000Phone: 1-(504)-593-7000Phone: 1-(504)-593-7000Account No. N1095Account No. N0605

WELL(S):	CA Nos.	or	RIVER BEND	Unit
Name: <u>RBU 15-10E</u>	API: <u>43-047-32190</u>	Entity: <u>7050</u>	S 10 T 10S R 19E	Lease: <u>U-013792</u>
Name: <u>RBU 3-17FX</u>	API: <u>43-047-32191</u>	Entity: <u>7050</u>	S 17 T 10S R 20E	Lease: <u>U-013769-C</u>
Name: <u>RBU 13-15E</u>	API: <u>43-047-32197</u>	Entity: <u>7050</u>	S 15 T 10S R 19E	Lease: <u>U-013766</u>
Name: <u>RBU 7-22E</u>	API: <u>43-047-32198</u>	Entity: <u>7050</u>	S 22 T 10S R 19E	Lease: <u>U-013792</u>
Name: <u>RBU 5-23E</u>	API: <u>43-047-32199</u>	Entity: <u>7050</u>	S 23 T 10S R 19E	Lease: <u>U-013766</u>
Name: <u>RBU 13-18F</u>	API: <u>43-047-32201</u>	Entity: <u>7050</u>	S 18 T 10S R 20E	Lease: <u>U-013793</u>
Name: <u>RBU 15-15E</u>	API: <u>43-047-32211</u>	Entity: <u>7050</u>	S 15 T 09S R 19E	Lease: <u>U-013766</u>
Name: <u>RBU 5-19F</u>	API: <u>43-047-32213</u>	Entity: <u>7050</u>	S 19 T 10S R 20E	Lease: <u>U-013769-A</u>
Name: <u>RBU 9-17F</u>	API: <u>43-047-32217</u>	Entity: <u>7050</u>	S 17 T 10S R 20E	Lease: <u>U-013769-C</u>
Name: <u>RBU 7-17F</u>	API: <u>43-047-32218</u>	Entity: <u>7050</u>	S 17 T 10S R 20E	Lease: <u>U-013769-C</u>
Name: <u>RBU 15-14E</u>	API: <u>43-047-32219</u>	Entity: <u>7050</u>	S 14 T 10S R 19E	Lease: <u>U-013792</u>
Name: <u>RBU 5-3E</u>	API: <u>43-047-32220</u>	Entity: <u>7050</u>	S 03 T 10S R 19E	Lease: <u>U-03505</u>
Name: <u>RBU 9-3E</u>	API: <u>43-047-32228</u>	Entity: <u>7050</u>	S 03 T 10S R 19E	Lease: <u>U-035316</u>
Name: <u>RBU 7-14E</u>	API: <u>43-047-32239</u>	Entity: <u>7050</u>	S 14 T 10S R 19E	Lease: <u>U-013792</u>
Name: <u>RBU 9-14F</u>	API: <u>43-047-32240</u>	Entity: <u>7050</u>	S 14 T 10S R 20E	Lease: <u>U-013397-A</u>
Name: <u>RBU 13-17F</u>	API: <u>43-047-32241</u>	Entity: <u>7050</u>	S 17 T 10S R 20E	Lease: <u>U-013769-C</u>
Name: <u>RBU 5-22E</u>	API: <u>43-047-32242</u>	Entity: <u>7050</u>	S 22 T 10S R 19E	Lease: <u>U-013792</u>

OPERATOR CHANGE DOCUMENTATION

- YES 1. A pending operator change file has been set up.
- YES 2. (R649-8-10) Sundry or other legal documentation has been received from the **FORMER** operator on 6-29-00.
- YES 3. (R649-8-10) Sundry or other legal documentation has been received from the **NEW** operator on 6-29-00.
- YES 4. The new company has been looked up in the **Department of Commerce, Division of Corporations Database** if the new operator above is not currently operating any wells in Utah. Is the operator registered with the State? **Yes/No** If yes, the company file number is SEE ATTACHED. If no, Division letter was mailed to the new operator on _____.

- YES 5. **Federal and Indian Lease Wells.** The BLM or the BIA has approved the merger, **name change** or operator change for all wells listed above involving Federal or Indian leases on 6-2-00.
- N/A 6. **Federal and Indian Units.** The BLM or the BIA has approved the successor of unit operator for all wells listed above involving unit operations on _____.
- N/A 7. **Federal and Indian Communitization Agreements ("CA").** The BLM or the BIA has approved the operator change for all wells listed above involved in the CA on _____.
- N/A 8. **Underground Injection Control ("UIC") Program.** The Division has approved UIC Form 5, Transfer of Authority to Inject, for the enhanced/secondary recovery unit/project and/or for the water disposal well(s) listed above.
- YES 9. Changes have been entered in the **Oil and Gas Information System** for each well listed on 7-31-00.
- YES 10. Changes have been included on the **Monthly Operator Change letter** on 7-31-00.

STATE BOND VERIFICATION

- N/A 1. State Well(s) covered by Bond No. _____.

FEE WELLS - BOND VERIFICATION / LEASE INTEREST OWNER NOTIFICATION

- N/A 1. (R649-3-1) The **NEW** operator of any fee lease well(s) listed above has furnished a proper bond.
- N/A 2. A copy of this form has been placed in the **new and former operator's bond files** on _____.
- N/A 3. The **FORMER** operator has requested a release of liability from their bond as of today's date _____? If yes, Division response was made to this request by letter dated _____. (see bond file).
- N/A 4. (R649-2-10) The **Former** operator of any Fee lease wells listed above has been contacted and informed by letter dated _____, of their responsibility to notify all interest owners of this change.
- N/A 5. Bond information added to **RBDMS** on _____.
- N/A 6. Fee wells attached to bond in **RBDMS** on _____.

FILMING

- ____ 1. All attachments to this form have been **microfilmed** on 2-23-01.

FILING

- ____ 1. **Originals/Copies** of all attachments pertaining to each individual well have been filed in each **well file**.
- ____ 2. The **original of this form** has been filed in the operator file and a copy in the old operator file.

COMMENTS

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0135
Expires November 30, 2000

SUNDRY NOTICES AND REPORTS ON WELLS
Do not use this form for proposal to drill or to re-enter an
abandoned well. Use Form 3160-3 (APD) for such proposals.

STUDENT TRIPLOATE: Filing Instructions on Reverse Side

1. Type of Well

☐ Oil Well ☒ Gas Well ☐ Other

2. Name of Operator

DOMINION EXPLORATION & PRODUCTION, INC.

3a. Address

16945 Northchase Drive, Suite 1750 Houston, Texas 77060

3b. Phone No. (include area code)

281-873-3692

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

646' FWL & 690' FSL

SW SW Sec. 17, T10S, R20E

5. Lease Serial No.

U-013769-C

6. If Indian, Allottee or Tribe Name

7. If Unit or CA/Agreement, Name and/or No.

RIVER BEND UNIT

8. Well Name and No.

RBU 13-17F

9. API Well No.

43-047-32241

10. Field and Pool, or Exploratory Area

NATUTAL BUTTES

11. County or Parish, State

UINTAH COUNTY, UTAH

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

☒ Notice of Intent

☐ Subsequent Report

☐ Final Abandonment Notice

TYPE OF ACTION

☐ Acidize

☐ Alter Casing

☐ Casing Repair

☐ Change Plans

☐ Convert to Injection

☐ Deepen

☐ Fracture Treat

☐ New Construction

☐ Plug and Abandon

☐ Plug Back

☐ Production (Start/Resume)

☐ Reclamation

☐ Recomplete

☐ Temporarily Abandon

☐ Water Disposal

☐ Water Shut-Off

☐ Well Integrity

☒ Other T&A well

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the final site is ready for final inspection.)

Operator requests permission to temporarily abandon the RBU 13-17F pending further evaluation of the location.

Accepted by the
Utah Division of
Oil, Gas and Mining

Date: 6/26/01

By: D. K. Dent

6/26/01
CAD

Federal Approval Of This
Action Is Necessary

RECEIVED

JUN 25 2001

DIVISION OF
OIL, GAS AND MINING

(1st Time req. permission to T&A per RAM)

14. I hereby certify that the foregoing is true and correct

Name (Printed/Typed)

Diann Flowers

Title

Regulatory Specialist

Signature

Diann Flowers

Date

06/19/2001

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved by

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Title

Date

Office

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB NO. 1004-0135
Expires: November 30, 2000

SUNDRY NOTICES AND REPORTS ON WELLS
Do not use this form for proposals to drill or to re-enter an abandoned well. Use form 3160-3 (APD) for such proposals.

SUBMIT IN TRIPLICATE - Other instructions on reverse side.

5. Lease Serial No. U-013769C
6. If Indian, Allottee or Tribe Name
7. If Unit or CA/Agreement, Name and/or No.
8. Well Name and No. RBU 13-17F
9. API Well No. 43-047-32241
10. Field and Pool, or Exploratory NATURAL BUTTES
11. County or Parish, and State UINTAH COUNTY, UT

1. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other	
2. Name of Operator DOMINION EXPL. & PROD., INC.	Contact: CARLA CHRISTIAN E-Mail: Carla_M_Christian@dom.com
3a. Address 14000 QUAIL SPRINGS PARKWAY, SUITE 600 OKLAHOMA CITY, OK 73134	3b. Phone No. (include area code) Ph: 405.749.5263 Fx: 405.749.6690
4. Location of Well (Footage, Sec., T., R., M., or Survey Description) Sec 17 T10S R20E SWSW 690FSL 646FWL	

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input type="checkbox"/> Other
	<input type="checkbox"/> Change Plans	<input checked="" type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	


13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

1/14/04 spot 40 sks of "G" cmt. on plug @ 6253', cmt top @ 5900'. Set CIBP @ 4018', spot 35 sks "G" cmt. on plug, cmt. top @ 3708'. Set CIBP @ 455'. Pump 55 sks "G" cmt, cmt top @ surface. Cut off well head. RIH w/80' 1" tbg., in the annulus between the 8 5/8" csg., & 5 1/2" csg., pump cmt. to surface, fill 5 1/2" csg., w/cmt. Weld on dry hie marker. Job witnessed by Jamie sparger and 5 BLM student.

RECEIVED

JAN 30 2004

DIV. OF OIL, GAS & MINING

14. I hereby certify that the foregoing is true and correct. Electronic Submission #27279 verified by the BLM Well Information System For DOMINION EXPL. & PROD., INC., sent to the Vernal	
Name (Printed/Typed) CARLA CHRISTIAN	Title AUTHORIZED REPRESENTATIVE
Signature  (Electronic Submission)	Date 01/28/2004

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved By _____	Title _____	Date _____
Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.		Office _____

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

**** OPERATOR-SUBMITTED ** OPERATOR-SUBMITTED ** OPERATOR-SUBMITTED ****